

**BID DATE: 06/04/2020
KINSLEY NO. 203055**

Line No.	Alt Code	Item No.	Short Description	QTY	Unit	Unit Price
1		0201-0001	CLEARING AND GRUBBING	1	LS	
2		0201-0002	CLEARING AND GRUBBING	1	LS	
3		0203-0001	CLASS 1 EXCAVATION	3209	CY	
4		0204-0150	CLASS 4 EXCAVATION	4	CY	
5		0205-0264	SELECTED BORROW EXCAVATION ROCK, CLASS R-4	387	CY	
6		4205-0300	SELECTED BORROW EXCAVATION (MODIFIED)	92	TON	
7		0212-0001	GEOTEXTILE, CLASS 1	796	LF	
8		0212-0014	GEOTEXTILE, CLASS 4, TYPE A	3488	SY	
9		0313-0422	SUPERPAVE ASPHALT MIXTURE DESIGN, BASE COURSE, PG 64S-22, 0.3 TO < 3 MILLION ESALs, 25.0 MM MIX, 4" DEPTH	921	SY	
10		0313-0430	SUPERPAVE ASPHALT MIXTURE DESIGN, BASE COURSE, PG 64S-22, 0.3 TO < 3 MILLION ESALs, 25.0 MM MIX, 8" DEPTH	908	SY	
11		0313-0432	SUPERPAVE ASPHALT MIXTURE DESIGN, BASE COURSE, PG 64S-22, 0.3 TO < 3 MILLION ESALs, 25.0 MM MIX, 9" DEPTH	1554	SY	
12		0350-0106	SUBBASE 6" DEPTH (NO. 2A)	852	SY	
13		0350-0108	SUBBASE 8" DEPTH (NO. 2A)	2462	SY	
14		0413-0230	SUPERPAVE ASPHALT MIXTURE DESIGN, WEARING COURSE, PG 64S-22, 0.3 TO < 3 MILLION ESALS, 12.5 MM MIX, 2" DEPTH, SRL-H	18185	SY	
15		0413-1024	SUPERPAVE ASPHALT MIXTURE DESIGN, WEARING COURSE (SCRATCH), PG 64S-22, 0.3 TO < 3 MILLION ESALS, 9.5 MM MIX, SRL-L	419	TON	
16		0413-2074	SUPERPAVE ASPHALT MIXTURE DESIGN, WEARING COURSE (LEVELING), PG 64S-22, 0.3 TO < 3 MILLION ESALS, 9.5 MM MIX, SRL-L	18	TON	
17		0413-6045	SUPERPAVE ASPHALT MIXTURE DESIGN, BINDER COURSE, PG 64S-22, 0.3 TO < 3 MILLION ESALS, 19.0 MM MIX, 2 1/2" DEPTH	2462	SY	
18		0460-0001	ASPHALT TACK COAT	28228	SY	
19		0491-0013	MILLING OF ASPHALT PAVEMENT SURFACE, 2" DEPTH, MILLED MATERIAL RETAINED BY CONTRACTOR	212	SY	
20		0491-0014	MILLING OF ASPHALT PAVEMENT SURFACE, 2 1/2" DEPTH, MILLED MATERIAL RETAINED BY CONTRACTOR	7958	SY	
21		0491-0019	MILLING OF ASPHALT PAVEMENT SURFACE, VARIABLE DEPTH, MILLED MATERIAL RETAINED BY CONTRACTOR	6019	SY	
22		0505-0001	BRIDGE APPROACH SLAB	156	SY	
23		0515-0001	SAWING AND SEALING OF ASPHALT OVERLAYS	648	LF	
24		0608-0001	MOBILIZATION	1	LS	
25		0609-0003	INSPECTOR'S FIELD OFFICE AND INSPECTION FACILITIES, TYPE B	1	LS	
26		0609-0009	EQUIPMENT PACKAGE	1	LS	
27		0610-7002	6" PAVEMENT BASE DRAIN	796	LF	
28		0610-7400	ADDITIONAL AGGREGATE FOR EXTRA DEPTH PAVEMENT BASE DRAIN	4	CY	
29		0612-0001	SUBGRADE DRAINS	280	LF	
30		0615-0022	6" SUBSURFACE DRAIN OUTLETS	164	LF	
31		0615-0040	SUBSURFACE DRAIN OUTLET ENDWALL	2	EA	
32		0615-0066	66" RED SUBSURFACE DRAIN OUTLET MARKER	5	EA	
33		0619-0459	PERMANENT IMPACT ATTENUATING DEVICE, TYPE II, TEST LEVEL 3, TANGENT (MASH)	5	EA	
34		0620-0010	TYPICAL AND ALTERNATE CONCRETE BRIDGE BARRIER TRANSITION WITHOUT INLET PLACEMENT	8	EA	
35		0620-0400	TERMINAL SECTION, SINGLE	3	EA	
36		0620-0503	REMOVE EXISTING GUIDE RAIL (CONTRACTOR'S PROPERTY)	1732	LF	
37		0620-1600	TYPE 31-S GUIDE RAIL	750	LF	
38		0620-1625	TYPE 31-SC GUIDE RAIL	100	LF	
39		0620-1670	TYPE 31-STRONG POST IN-LINE ANCHOR	2	EA	
40		0627-3020	TEMPORARY BARRIER, TEST LEVEL 3, BARRIER DEFLECTION DISTANCE < /=2'	300	LF	
41		0627-3050	TEMPORARY BARRIER, TEST LEVEL 3, BARRIER DEFLECTION DISTANCE < /=5'	339	LF	
42		0628-3020	RESET TEMPORARY BARRIER, TEST LEVEL 3, BARRIER DEFLECTION DISTANCE < /=2'	209	LF	
43		0643-0001	TEMPORARY CONCRETE BARRIER, STRUCTURE MOUNTED	69	LF	
44		0644-0001	TEMPORARY CONCRETE BARRIER, STRUCTURE MOUNTED, RESET	20	LF	

PENNDOT SR 422-033 LEBANON COUNTY

BID ITEMS

PENNDOT PROJECT NO. 100342

BID DATE: 06/04/2020
KINSLEY NO. 203055

Line No.	Alt Code	Item No.	Short Description	QTY	Unit	Unit Price
45		0686-0020	CONSTRUCTION SURVEYING, TYPE B	1	LS	
46		0686-0050	CONSTRUCTION SURVEYING, TYPE D	1	LS	
47		0686-0051	CONSTRUCTION SURVEYING, TYPE D	1	LS	
48		0689-0003	CPM SCHEDULE	1	LS	
49		0690-0001	INTERNAL FACILITATION	1000	DOL	1
50		0696-0580	TEMPORARY IMPACT ATTENUATING DEVICE, TYPE IV, TEST LEVEL 3	4	EA	
51		0697-0580	RESET TEMPORARY IMPACT ATTENUATING DEVICE, TYPE IV, TEST LEVEL 3	2	EA	
52		0802-0001	TOPSOIL FURNISHED AND PLACED	613	CY	
53		0804-0001	SEEDING AND SOIL SUPPLEMENTS - FORMULA B, INCLUDING MULCH	240	LB	
54		0804-0003	SEEDING AND SOIL SUPPLEMENTS - FORMULA D, INCLUDING MULCH	93	LB	
55		0804-0004	SEEDING - FORMULA E, INCLUDING MULCH	72	LB	
56		0804-0007	SEEDING AND SOIL SUPPLEMENTS - FORMULA W, INCLUDING MULCH	6	LB	
57		0806-0121	TEMP. EXTENDED-TERM, ROLLED EROSION CONTROL PRODUCT TYPE 3B	628	SY	
58		0806-0140	PERMANENT ROLLED EROSION CONTROL PRODUCT, TYPE 5A	246	SY	
59		0811-0003	TEMPORARY PROTECTIVE FENCE	441	LF	
60		0845-0001	UNFORESEEN WATER POLLUTION CONTROL	6000	DOL	1
61		0849-0010	ROCK CONSTRUCTION ENTRANCE	2	EA	
62		0855-0003	PUMPED WATER FILTER BAG	3	EA	
63		0855-0004	REPLACEMENT PUMPED WATER FILTER BAG	3	EA	
64		0860-0000	INLET FILTER BAG FOR TYPE M INLET	2	EA	
65		0867-0012	COMPOST FILTER SOCK, 12" DIAMETER	1766	LF	
66		0901-0001	MAINTENANCE AND PROTECTION OF TRAFFIC DURING CONSTRUCTION	1	LS	
67		0901-0002	MAINTENANCE AND PROTECTION OF TRAFFIC DURING CONSTRUCTION	1	LS	
68		0901-0240	ADDITIONAL TRAFFIC CONTROL SIGNS	200	SF	
69		0901-0320	4" STANDARD PAVEMENT MARKINGS, PAINT & BEADS, YELLOW	14075	LF	
70		0901-0330	4" STANDARD PAVEMENT MARKINGS, PAINT & BEADS, WHITE	12195	LF	
71		0901-0331	6" STANDARD PAVEMENT MARKINGS, PAINT & BEADS, WHITE	595	LF	
72		0901-0334	24" STANDARD PAVEMENT MARKINGS, PAINT & BEADS, WHITE	64	LF	
73		0901-0461	FULL-MATRIX CHANGEABLE MESSAGE SIGN W/O TELECOMMUNICATIONS	4	EA	
74		0901-0701	TEMPORARY TRAFFIC SIGNALS (PERMANENT ONLY)	1	EA	
75		0931-0001	POST MOUNTED SIGNS, TYPE B	10	SF	
76		0937-0330	FLEXIBLE DELINEATOR POST, GROUND-MOUNT TYPE GM-2, WHITE POST WITH WHITE/BLANK SHEETING	11	EA	
77		0937-0337	FLEXIBLE DELINEATOR POST, GROUND-MOUNT TYPE GM-2, RED POST WITH RED/WHITE SHEETING	4	EA	
78		0954-0012	2 INCH CONDUIT	245	LF	
79		0954-0151	TRENCH AND BACKFILL, TYPE I	226	LF	
80		0954-0152	TRENCH AND BACKFILL, TYPE II	21	LF	
81		0954-0201	SIGNAL CABLE, 14 AWG, 3 CONDUCTOR	315	LF	
82		0954-0301	JUNCTION BOX, JB-26	4	EA	
83		0956-0001	DETECTOR LEAD IN CABLE	21	LF	
84		0956-0101	LOOP SENSOR	153	LF	
85		0960-0021	24" WHITE HOT THERMOPLASTIC PAVEMENT MARKINGS	92	LF	
86		0960-0222	WHITE HOT THERMOPLASTIC LEGEND, "RIGHT ARROW", 12' - 0" X 3' - 0"	4	EA	
87		0960-0224	WHITE HOT THERMOPLASTIC LEGEND, "LEFT ARROW", 12' - 0" X 3' - 0"	9	EA	
88		0962-1000	4" WHITE WATERBORNE PAVEMENT MARKINGS	5275	LF	
89		0962-1001	6" WHITE WATERBORNE PAVEMENT MARKINGS	595	LF	
90		0962-1005	4" YELLOW WATERBORNE PAVEMENT MARKINGS	6695	LF	
91		0962-1062	WHITE WATERBORNE PAVEMENT LEGEND, "LEFT ARROW", 12'-0" X 3'-0"	4	EA	
92		0962-1063	WHITE WATERBORNE PAVEMENT LEGEND, "THRU AND RIGHT ARROW", 20'-0" X 3'-7"	4	EA	
93		0963-0001	PAVEMENT MARKING REMOVAL	1972	SF	
94		0963-0004	4" PAVEMENT MARKING REMOVAL	1433	LF	
95		0963-0010	PAVEMENT MARKING REMOVAL (LEGENDS AND SYMBOLS)	10	EA	
96		1001-1140	CLASS C CEMENT CONCRETE	27	CY	
97		1018-0051	REMOVAL OF PORTION OF EXISTING BRIDGE	1	LS	
98		1018-0052	REMOVAL OF PORTION OF EXISTING BRIDGE	1	LS	

PENNDOT SR 422-033 LEBANON COUNTY

BID ITEMS

PENNDOT PROJECT NO. 100342

PAGE 2 OF 4

**BID DATE: 06/04/2020
KINSLEY NO. 203055**

Line No.	Alt Code	Item No.	Short Description	QTY	Unit	Unit Price
99		1999-0000	TRAINEES FOR PROJECTS 100% STATE FUNDED	1000	HR	
100	10	8010-0001	BRIDGE STRUCTURE, AS DESIGNED, S-37876	1	LS	
		0204-0100	CLASS 3 EXCAVATION	812	CY	
		1001-1000	CLASS AAAP CEMENT CONCRETE	230	CY	
		1001-1080	CLASS AA CEMENT CONCRETE	40	CY	
		1001-1120	CLASS A CEMENT CONCRETE	88	CY	
		0205-0292	STRUCTURE BACKFILL	204	CY	
		0680-0121	MEMBRANE WATERPROOFING SYSTEM INSTALLED ON OTHER SURFACES	32	SY	
		4205-0268	SELECTED BORROW EXCAVATION ROCK, CLASS R-8 CHOKED WITH R-4 ROCK	168	CY	
		0205-0285	SELECTED BORROW EXCAVATION, COARSE AGGREGATE, NO. 57	86	CY	
		1080-0431	PRESTRESSED CONCRETE SPREAD BOX BEAMS, 48" X 17"	253	LF	
		1001-0611	6" STRUCTURE FOUNDATION DRAIN	200	LF	
		1019-0040	PROTECTIVE COATING FOR REINFORCED CONCRETE SURFACES (PENETRATING SEALERS, REINFORCED CONCRETE SUBSTRUCTURE SURFACES)	27	SY	
		1019-0050	PROTECTIVE COATING FOR REINFORCED CONCRETE SURFACES (PENETRATING SEALERS, BRIDGE SUPERSTRUCTURE)	359	SY	
101	10	1002-0053	REBAR, EPOXY COATED	72777	LB	
102	10	1005-1825	STEEL HP12X74 PRODUCTION PILE	308	LF	
103	11	8000-0001	PRESTRESSED CONCRETE BRIDGE STRUCTURE	1	LS	
104	11	8100-0001	STEEL BRIDGE STRUCTURE	1	LS	
105	20	8010-0002	BRIDGE STRUCTURE, AS DESIGNED, S-38110	1	LS	
		0204-0100	CLASS 3 EXCAVATION	1960	CY	
		0680-0121	MEMBRANE WATERPROOFING SYSTEM INSTALLED ON OTHER SURFACES	59	SY	
		0205-0285	SELECTED BORROW EXCAVATION, COARSE AGGREGATE, NO. 57	4	CY	
		0205-0266	SELECTED BORROW EXCAVATION ROCK, CLASS R-6	6	CY	
		4205-0268	SELECTED BORROW EXCAVATION ROCK, CLASS R-8 CHOKED WITH ROCK CLASS R-4	310	CY	
		1001-1000	CLASS AAAP CEMENT CONCRETE	168	CY	
		1001-1080	CLASS AA CEMENT CONCRETE	48	CY	
		1001-1120	CLASS A CEMENT CONCRETE	176	CY	
		0205-0292	STRUCTURE BACKFILL	775	CY	
		0910-5255	2" CONDUIT IN STRUCTURE	70	LF	
		1005-1725	STEEL HP12X74 TEST PILE	1	EA	
		1080-0431	PRESTRESSED CONCRETE SPREAD BOX BEAMS, 48" X 17"	334	LF	
		1001-0611	6" STRUCTURE FOUNDATION DRAIN	76	LF	
		1019-0050	PROTECTIVE COATING FOR REINFORCED CONCRETE SURFACES (PENETRATING SEALERS, BRIDGE SUPERSTRUCTURE)	539	SY	
		1019-0040	PROTECTIVE COATING FOR REINFORCED CONCRETE SURFACES (PENETRATING SEALERS, REINFORCED CONCRETE SUBSTRUCTURE SURFACES)	71	SY	
		1001-0980	MECHANICAL TEXTURING WITH LONGITUDINAL SAWED GROOVES	255	SY	
106	20	1002-0151	MECHANICAL SPLICE SYSTEM FOR NO. 4 REBAR, EPOXY COATED	24	EA	
107	20	1002-0152	MECHANICAL SPLICE SYSTEM FOR NO. 5 REBAR, EPOXY COATED	157	EA	
108	20	1002-0153	MECHANICAL SPLICE SYSTEM FOR NO. 6 REBAR, EPOXY COATED	4	EA	
109	20	1002-0154	MECHANICAL SPLICE SYSTEM FOR NO. 7 REBAR, EPOXY COATED	22	EA	
110	20	1002-0155	MECHANICAL SPLICE SYSTEM FOR NO. 8 REBAR, EPOXY COATED	16	EA	
111	20	1002-0156	MECHANICAL SPLICE SYSTEM FOR NO. 9 REBAR, EPOXY COATED	8	EA	
112	20	1002-0190	REBAR, EPOXY COATED	60989	LB	
113	20	1002-0220	STAINLESS STEEL REBAR	145	LB	
114	20	1005-1826	STEEL HP12X74 PRODUCTION PILE	192	LF	
115	20	1005-1925	STEEL HP12X74 PILE TIP REINFORCEMENT (NORMAL DUTY)	11	EA	
116	21	8100-0002	STEEL BRIDGE STRUCTURE	1	LS	
117	22	8000-0002	PRESTRESSED CONCRETE BRIDGE STRUCTURE	1	LS	
118		9000-0001	TEMPORARY DIVERSION DEVICE	1	LS	
119		9000-0002	TEMPORARY DIVERSION DEVICE	1	LS	
120		9000-0003	UTILITY VAULT REMOVAL	1	LS	
121		9000-0004	TEMPORARY MAILBOX RELOCATION AND RESET	3	EA	
122		9000-0005	BARRICADE REMOVAL	2	EA	

**BID DATE: 06/04/2020
KINSLEY NO. 203055**

Line No.	Alt Code	Item No.	Short Description	QTY	Unit	Unit Price
123		9000-0006	SNOWPLOW TRUCK AND OPERATOR	750	HR	
124		9000-0101	PRE-AUGERING FOR INTEGRAL ABUTMENTS	232	LF	
125		9000-0102	PRE-AUGERING FOR INTEGRAL ABUTMENTS	180	LF	
126		9000-0120	SOLUTION CAVITY EXCAVATION	33	CY	
127		9000-0121	SOLUTION CAVITY EXCAVATION	33	CY	
128		9005-0001	EXPLORATORY AIR TRACK DRILLING	372	LF	
129		9005-0002	EXPLORATORY AIR TRACK DRILLING	312	LF	
130		9203-0101	TEMPORARY EXCAVATION SUPPORT AND PROTECTION SYSTEM	1	LS	
131		9203-2102	TEMPORARY EXCAVATION SUPPORT AND PROTECTION SYSTEM	1	LS	
132		9204-0100	CLASS 3, OVEREXCAVATION FOR PLACEMENT OF CLASS C CEMENT CONCRETE	5	CY	