

**BID DATE: 05/21/2020
KINSLEY NO. 203054**

Line No.	Alt Code	Item No.	Short Description	QTY	Unit	Unit Price
1		0201-0001	CLEARING AND GRUBBING	1	LS	
2		0203-0001	CLASS 1 EXCAVATION	2572	CY	
3		0205-0264	SELECTED BORROW EXCAVATION ROCK, CLASS R-4	13	CY	
4		4205-0300	SELECTED BORROW EXCAVATION (MODIFIED)	90	TON	
5		0205-0364	SELECTED BORROW EXCAVATION ROCK, CLASS R-4	5	TON	
6		0205-0390	SELECTED BORROW EXCAVATION, COARSE AGGREGATE, NO. 2A	90	TON	
7		0206-0010	SELECT GRANULAR MATERIAL (2RC)	389	TON	
8		0212-0014	GEOTEXTILE, CLASS 4, TYPE A	240	SY	
9		0313-0422	SUPERPAVE ASPHALT MIXTURE DESIGN, BASE COURSE, PG 64S-22, 0.3 TO < 3 MILLION ESALS, 25.0 MM MIX, 4" DEPTH	9204	SY	
10		0316-0437	SUPERPAVE ASPHALT MIXTURE DESIGN, FLEXIBLE BASE REPLACEMENT, PG 64S-22, 0.3 TO < 3 MILLION ESALS, 25.0 MM MIX	829	TON	
11		0350-0106	SUBBASE 6" DEPTH (NO. 2A)	9204	SY	
12		0404-0012	ASPHALT PAVEMENT RIDE QUALITY INCENTIVE, SCHEDULE B	20000	DOL	1
13		0405-0001	ASPHALT PAVEMENT LONGITUDINAL JOINT DENSITY INCENTIVE/DISINCENTIVE	20000	DOL	1
14		0413-0258	SUPERPAVE ASPHALT MIXTURE DESIGN, WEARING COURSE, PG 64S-22, 0.3 TO < 3 MILLION ESALS, 9.5 MM MIX, SRL-L	440	TON	
15		0413-1024	SUPERPAVE ASPHALT MIXTURE DESIGN, WEARING COURSE (SCRATCH), PG 64S-22, 0.3 TO < 3 MILLION ESALS, 9.5 MM MIX, SRL-L	1833	TON	
16		0413-3220	SUPERPAVE ASPHALT MIXTURE DESIGN, WEARING COURSE, RPS, PG 64S-22, 0.3 TO < 3 MILLION ESALS, 12.5 MM MIX, 2" DEPTH, SRL-H	40715	SY	
17		0460-0001	ASPHALT TACK COAT	83527	SY	
18		0461-0001	ASPHALT PRIME COAT	2907	SY	
19		0492-0030	PROFILE MILLING, MILLED MATERIAL RETAINED BY CONTRACTOR	399	SY	
20		0601-5901	CLEANING EXISTING PIPE CULVERTS, DIAMETERS UP TO AND INCLUDING 36"	480	LF	
21		0608-0001	MOBILIZATION	1	LS	
22		0609-0007	INSPECTOR'S FIELD OFFICE AND INSPECTION FACILITIES, TYPE B	1	LS	
23		0609-0009	EQUIPMENT PACKAGE	1	LS	
24		0619-0459	PERMANENT IMPACT ATTENUATING DEVICE, TYPE II, TEST LEVEL 3, TANGENT (MASH)	10	EA	
25		0620-0400	TERMINAL SECTION, SINGLE	4	EA	
26		4620-0500	RESET GUIDE RAIL ((MASH 31-S STANDARDS))	25	LF	
27		0620-0503	REMOVE EXISTING GUIDE RAIL (CONTRACTOR'S PROPERTY)	5013	LF	
28		0620-0872	BURIED-IN-BACKSLOPE TERMINAL, SINGLE PANEL	1	EA	
29		0620-1600	TYPE 31-S GUIDE RAIL	4400	LF	
30		0620-1601	TYPE 31-S GUIDE RAIL WITH 7' EXTRA LENGTH POSTS	50	LF	
31		0620-1625	TYPE 31-SC GUIDE RAIL	100	LF	
32		0620-1635	TYPE 31-SCC GUIDE RAIL	100	LF	
33		0620-1670	TYPE 31-STRONG POST IN-LINE ANCHOR	4	EA	
34		0686-0040	CONSTRUCTION SURVEYING, TYPE C	1	LS	
35		0689-0003	CPM SCHEDULE	1	LS	
36		0690-0001	INTERNAL FACILITATION	1000	DOL	1
37		0703-0024	NO. 2A COARSE AGGREGATE	152	CY	
38		0802-0001	TOPSOIL FURNISHED AND PLACED	417	CY	
39		0804-0001	SEEDING AND SOIL SUPPLEMENTS - FORMULA B, INCLUDING MULCH	126	LB	
40		0810-0024	TREE TRIMMING TO AN UNLIMITED HEIGHT	1	LS	
41		0901-0001	MAINTENANCE AND PROTECTION OF TRAFFIC DURING CONSTRUCTION	1	LS	
42		0901-0320	4" STANDARD PAVEMENT MARKINGS, PAINT & BEADS, YELLOW	58730	LF	
43		0901-0330	4" STANDARD PAVEMENT MARKINGS, PAINT & BEADS, WHITE	29270	LF	
44		0931-0003	POST MOUNTED SIGNS, TYPE B, STEEL SQUARE POST	28	SF	
45		0935-0001	POST MOUNTED SIGNS, TYPE F	43	SF	
46		0937-0330	FLEXIBLE DELINEATOR POST, GROUND-MOUNT TYPE GM-2, WHITE POST WITH WHITE/BLANK SHEETING	5	EA	
47		0937-0339	FLEXIBLE DELINEATOR POST, GROUND-MOUNT TYPE GM-2, RED POST WITH WHITE/BLANK SHEETING	21	EA	
48		0960-0021	24" WHITE HOT THERMOPLASTIC PAVEMENT MARKINGS	268	LF	
49		0962-1000	4" WHITE WATERBORNE PAVEMENT MARKINGS	29270	LF	

PENNDOT SR 1015-017 ADAMS COUNTY

BID ITEMS

PENNDOT PROJECT NO. 113260

PAGE 1 OF 2

**BID DATE: 05/21/2020
KINSLEY NO. 203054**

Line No.	Alt Code	Item No.	Short Description	QTY	Unit	Unit Price
50		0962-1001	6" WHITE WATERBORNE PAVEMENT MARKINGS	170	LF	
51		0962-1002	8" WHITE WATERBORNE PAVEMENT MARKINGS	266	LF	
52		0962-1005	4" YELLOW WATERBORNE PAVEMENT MARKINGS	29390	LF	
53		0965-0113	WHITE PREFORMED THERMOPLASTIC LEGEND, "MPH", 8' - 0"	2	EA	
54		0965-0150	WHITE PREFORMED THERMOPLASTIC LEGEND, "RR CROSSING", 6' - 6", 10' LANE WIDTH (INCLUDES "X", "RR", AND 2 TRANSVERSE BANDS)	2	EA	
55		0965-0303	WHITE PREFORMED THERMOPLASTIC LEGEND, "3", 8' - 0"	2	EA	
56		0965-0305	WHITE PREFORMED THERMOPLASTIC LEGEND, "5", 8' - 0"	2	EA	
57		0965-0412	WHITE PREFORMED THERMOPLASTIC LEGEND, "L", 8' - 0"	2	EA	
58		0965-0415	WHITE PREFORMED THERMOPLASTIC LEGEND, "O", 8' - 0"	2	EA	
59		0965-0419	WHITE PREFORMED THERMOPLASTIC LEGEND, "S", 8' - 0"	2	EA	
60		0965-0423	WHITE PREFORMED THERMOPLASTIC LEGEND, "W", 8' - 0"	2	EA	
61		0971-0001	REMOVE POST MOUNTED SIGNS, TYPE B	1	EA	
62		1001-1140	CLASS C CEMENT CONCRETE	120	CY	
63		9000-0001	SOLUTION CAVITY EXCAVATION	360	CY	
64		9605-2731	REBUILT INLET TYPE M CONCRETE TOP UNIT AND BICYCLE SAFE GRATE	7	EA	
65		9901-0350	RAILROAD PROTECTIVE SERVICES	8000	DOL	1