

**BID DATE: 09/17/2020**  
**KINSLEY NO. 203092**

Line No.	Alt Code	Item No.	Short Description	QTY	Unit	Unit Price
1		0201-0001	CLEARING AND GRUBBING	1	LS	
2		0203-0004	CLASS 1B EXCAVATION	726	CY	
3		0212-0001	GEOTEXTILE CLASS 1	1842	LF	
4		0220-0020	FLOWABLE BACKFILL TYPE C	3	CY	
5		0313-0426	SP BASE PG64S-22 0.3TO<3 MILLION ESALs 25.0 MM 6" DEPTH	681	SY	
6		0316-0437	SP FLEXIBLE BASE REPLACEMENT PG64S-22 0.3TO<3 MILLION ESALs 25.0 MM	118	TON	
7		0350-0106	SUBBASE 6" DEPTH (NO. 2A)	681	SY	
8		0413-0383	SP WEARING PG64E-22 0.3TO<3 MILLION ESALS 9.5 MM 1 1/2" DEPTH SRL-H	4648	SY	
9		0413-1024	SP WEARING (SCRATCH) PG64S-22 0.3TO<3 MILLION ESALS 9.5 MM SRL-L	105	TON	
10		0460-0001	ASPHALT TACK COAT	9295	SY	
11		0491-0013	MILLING OF ASPHALT PAVEMENT SURFACE 2" DEPTH MILLED MATERIAL RETAINED BY CONTRACTOR	3968	SY	
12		0601-7016	18" REINFORCED CONCRETE PIPE TYPE A 25' - 1.5' FILL 100 YEAR DESIGN LIFE	131	LF	
13		0604-7013	18" RCP TYPE A (OPEN JOINT) 2'-1.5' FILL 100 YR DESIGN LIFE	29	LF	
14		0605-2711	TYPE C CONCRETE TOP UNIT AND BICYCLE SAFE GRATE	11	SET	
15		0605-2850	STANDARD INLET BOX HEIGHT < / = 10'	13	EA	
16		4605-2858	TYPE 5 INLET BOX HEIGHT < / = 10' (MODIFIED)	1	EA	
17		4605-2859	TYPE 5 INLET BOX HEIGHT > 10' AND < / = 20' (MODIFIED)	2	EA	
18		0608-0001	MOBILIZATION	1	LS	
19		0609-0007	INSPECTOR'S FIELD OFFICE AND INSPECTION FACILITIES TYPE B	1	LS	
20		0609-0009	EQUIPMENT PACKAGE	1	LS	
21		0610-7002	6" PAVEMENT BASE DRAIN	1813	LF	
22		0630-0001	PLAIN CEMENT CONCRETE CURB	1917	LF	
23		0676-0001	CEMENT CONCRETE SIDEWALK	1999	SY	
24		0686-0020	CONSTRUCTION SURVEYING TYPE B	1	LS	
25		0689-0003	CPM SCHEDULE	1	LS	
26		0690-0001	INTERNAL FACILITATION	1000	DOL	1
27		0703-0025	NO. 57 COARSE AGGREGATE	4	CY	
28		0802-0001	TOPSOIL FURNISHED AND PLACED	9	CY	
29		0804-0006	SEEDING AND SOIL SUPPLEMENTS - FORMULA L INCLUDING MULCH	15	LB	
30		0845-0001	UNFORESEEN WATER POLLUTION CONTROL	1500	DOL	1
31		0855-0003	PUMPED WATER FILTER BAG	1	EA	
32		0860-0002	INLET FILTER BAG FOR TYPE C INLET	11	EA	
33		0901-0001	MAINTENANCE AND PROTECTION OF TRAFFIC DURING CONSTRUCTION	1	LS	
34		0901-0240	ADDITIONAL TRAFFIC CONTROL SIGNS	100	SF	
35		0901-0320	4" STANDARD PAVEMENT MARKINGS PAINT & BEADS YELLOW	4334	LF	
36		0901-0331	6" STANDARD PAVEMENT MARKINGS PAINT & BEADS WHITE	818	LF	
37		0931-0001	POST MOUNTED SIGNS TYPE B	77	SF	
38		0935-0001	POST MOUNTED SIGNS TYPE F	27	SF	
39		0941-0001	RESET POST MOUNTED SIGNS TYPE B	2	EA	
40		0945-0001	RESET POST MOUNTED SIGNS TYPE F	2	EA	
41		0954-0013	3 INCH CONDUIT	1052	LF	
42		0954-0151	TRENCH AND BACKFILL TYPE I	1024	LF	
43		0954-0153	TRENCH AND BACKFILL TYPE III	28	LF	
44		0954-0302	JUNCTION BOX JB-27	4	EA	
45		0956-0101	LOOP SENSOR	155	LF	
46		0960-0021	24" WHITE HOT THERMOPLASTIC PAVEMENT MARKINGS	53	LF	
47		0960-0224	WHITE HOT THERMOPLASTIC LEGEND "LEFT ARROW" 12' - 0" X 3' - 0"	13	EA	
48		0962-1001	6" WHITE WATERBORNE PAVEMENT MARKINGS	818	LF	
49		0962-1005	4" YELLOW WATERBORNE PAVEMENT MARKINGS	4334	LF	
50		0963-0001	PAVEMENT MARKING REMOVAL	445	SF	
51		0971-0001	REMOVE POST MOUNTED SIGNS TYPE B	1	EA	
52		1019-0020	PROTECTIVE COATING FOR REINFORCED CONCRETE SURFACES (EPOXY RESIN)	1410	SY	
53		1070-0200	PAINTING EXISTING STRUCTURAL STEEL	1	LS	
54		1072-0100	CONTAINMENT	1	LS	
55		1072-0200	WASTE MANAGEMENT	1	LS	
56		1072-0300	WORKER HEALTH AND SAFETY	1	LS	

**BID DATE: 09/17/2020  
KINSLEY NO. 203092**

<b>Line No.</b>	<b>Alt Code</b>	<b>Item No.</b>	<b>Short Description</b>	<b>QTY</b>	<b>Unit</b>	<b>Unit Price</b>
57		9000-0001	WASTE MANAGEMENT - SOIL	50000	DOL	1
58		9000-0002	UNFORESEEN BRIDGE REPAIRS	10000	DOL	1
59		9000-0003	CLEAN AND BLAST CONCRETE AND MASONRY WALLS	1410	SY	
60		9000-0300	INLET HOOD	11	EA	
61		9000-0301	CONCRETE COLLAR FOR INLET CONNECTION	8	EA	
62		9000-0302	TRENCH DRAIN	42	LF	
63		9000-1001	GRADE ADJUSTMENT OF SEWER MANHOLE	4	EA	
64		9000-1002	GRADE ADJUSTMENT OF WATER VALVE BOX	13	EA	
65		9000-1003	WATER LINE RELOCATIONS	1	LS	
66		9000-1004	COMBINED STORM AND SANITARY SEWER BYPASS PUMPING	1	LS	
67		9000-1005	SEWER MANHOLE FRAME AND COVER	5	SET	
68		9090-0610	CLASS A CEMENT CONCRETE REPAIRS	118	CF	
69		9203-0001	TEMPORARY EXCAVATION SUPPORT AND PROTECTION SYSTEM	1	LS	
70		9676-0001	CEMENT CONCRETE SIDEWALK MODIFIED	155	SY	