

**BID DATE: 02/11/2021
KINSLEY NO. 213014**

Line No.	Alt Code	Item No.	Short Description	QTY	Unit	Unit Price
1		0201-0001	CLEARING AND GRUBBING	1	LS	
2		0203-0004	CLASS 1B EXCAVATION	45	CY	
3		0204-0010	CLEANING EXISTING DITCHES EXCAVATION	80	LF	
4		0212-0014	GEOTEXTILE CLASS 4 TYPE A	84	SY	
5		0213-0002	TEMPORARY PROJECT AIR POLLUTION CONTROL	1000	DOL	1
6		0313-0030	SUPERPAVE ASPHALT MIXTURE DESIGN BASE PG58S-28 <0.3 MILLION ESALS 25.0 MM MIX 8" DEPTH	84	SY	
7		0350-0111	SUBBASE 11" DEPTH (NO. 2A)	84	SY	
8		0413-0246	SUPERPAVE ASPHALT MIXTURE DESIGN WEARING PG64S-22 0.3TO<3 MILLION ESALS 9.5 MM MIX 1 1/2" DEPTH SRL-G	1324	SY	
9		0413-2074	SUPERPAVE ASPHALT MIXTURE DESIGN WEARING (LEVELING) PG64S-22 0.3TO<3 MILLION ESALS 9.5 MM MIX SRL-L	80	TON	
10		0460-0003	ASPHALT TACK COAT (NTT/CNTT)	2648	SY	
11		0491-0014	MILLING OF ASPHALT PAVEMENT SURFACE 2 1/2" DEPTH MILLED MATERIAL RETAINED BY CONTRACTOR	1324	SY	
12		0601-7313	18" REINFORCED CONCRETE PIPE TYPE B 15'-1.5' FILL	8	LF	
13		0605-2600	TYPE D ENDWALL	1	EA	
14		0608-0001	MOBILIZATION	1	LS	
15		0609-0007	INSPECTOR'S FIELD OFFICE AND INSPECTION FACILITIES TYPE B	1	LS	
16		0609-0009	EQUIPMENT PACKAGE	1	LS	
17		0619-0459	PERM. IMPACT ATTENUATING DEVICE TYPE II TEST LEVEL 3 TANGENT (MASH)	3	EA	
18		0620-0010	TYPICAL AND ALTERNATE CONCRETE BRIDGE BARRIER TRANSITION WITHOUT INLET PLACEMENT	2	EA	
19		0620-0015	THRIE-BEAM TO VERTICAL WALL BRIDGE BARRIER TRANSITION	2	EA	
20		0620-0400	TERMINAL SECTION SINGLE	7	EA	
21		0620-0503	REMOVE EXISTING GUIDE RAIL (CONTRACTOR'S PROPERTY)	1865	LF	
22		0620-1600	TYPE 31-S GUIDE RAIL	1651	LF	
23		0620-1625	TYPE 31-SC GUIDE RAIL	50	LF	
24		0620-1670	TYPE 31-STRONG POST IN-LINE ANCHOR	4	EA	
25		0627-3020	TEMPORARY BARRIER TEST LEVEL 3 BARRIER DEFLECTION DISTANCE </=2'	1000	LF	
26		0628-3020	RESET TEMP. BARRIER TEST LEVEL 3 BARRIER DEFLECTION DISTANCE </=2'	1000	LF	
27		0686-0060	CONSTRUCTION SURVEYING TYPE D MODIFIED	1	LS	
28		0689-0003	CPM SCHEDULE	1	LS	
29		0690-0001	INTERNAL FACILITATION	2000	DOL	1
30		0696-0610	TEMPORARY IMPACT ATTENUATING DEVICE TYPE V (STANDARD) TEST LEVEL 3	2	EA	
31		0697-0610	RESET TEMP. IMPACT ATTENUATING DEVICE TYPE V (STANDARD) TEST LEVEL 3	2	EA	
32		0810-0027	TREE TRIMMING TO AN UNLIMITED HEIGHT	600	LF	
33		0845-0001	UNFORESEEN WATER POLLUTION CONTROL	1000	DOL	1
34		0901-0001	MAINTENANCE AND PROTECTION OF TRAFFIC DURING CONSTRUCTION	1	LS	
35		0901-0240	ADDITIONAL TRAFFIC CONTROL SIGNS	50	SF	
36		0901-0330	4" STANDARD PAVEMENT MARKINGS PAINT & BEADS WHITE	380	LF	
37		0901-0331	6" STANDARD PAVEMENT MARKINGS PAINT & BEADS WHITE	2000	LF	
38		0901-0334	24" STANDARD PAVEMENT MARKINGS PAINT & BEADS WHITE	24	LF	
39		0901-0461	FULL-MATRIX CHANGEABLE MESSAGE SIGN WITHOUT TELECOMMUNICATIONS	2	EA	
40		0901-0702	TEMPORARY TRAFFIC SIGNALS (PORTABLE ONLY)	1	EA	
41		0901-0712	TEMPORARY TRAFFIC CONTROL SIGNAL RESET (PORTABLE ONLY)	1	EA	
42		0931-0001	POST MOUNTED SIGNS TYPE B	16	SF	
43		0932-0001	POST MOUNTED SIGNS TYPE C	5	SF	
44		0935-0001	POST MOUNTED SIGNS TYPE F	31	SF	
45		4937-0113	GUIDE RAIL MOUNTED DELINEATOR TYPE D (W/B) (MODIFIED)	33	EA	
46		0937-0230	BARRIER MOUNTED DELINEATOR TOP-MOUNT TYPE P (W/W)	30	EA	
47		0962-1000	4" WHITE WATERBORNE PAVEMENT MARKINGS	5260	LF	
48		0962-1005	4" YELLOW WATERBORNE PAVEMENT MARKINGS	5260	LF	
49		0963-0001	PAVEMENT MARKING REMOVAL	351	SF	
50		1001-0980	MECHANICAL TEXTURING WITH LONGITUDINAL SAWED GROOVES	3572	SY	
51		5016-0006	BARRIER PROTECTIVE FENCE VINYL-COATED STEEL (MODIFIED)	200	LF	
52		1019-0020	PROTECTIVE COATING FOR REINFORCED CONCRETE SURFACES (EPOXY RESIN)	960	SY	

PENNDOT SR 17-016 PERRY COUNTY

BID ITEMS

PENNDOT PROJECT NO. 100167

PAGE 1 OF 2

**BID DATE: 02/11/2021
KINSLEY NO. 213014**

Line No.	Alt Code	Item No.	Short Description	QTY	Unit	Unit Price
53		1039-0010	CONCRETE BRIDGE DECK SURFACE PREPARATION HYDRODEMOLITION	3572	SY	
54		1042-0002	LATEX MODIFIED CONCRETE WEARING SURFACE 1 1/2" DEPTH	3572	SY	
55		1042-0060	LATEX MODIFIED CONCRETE VARIABLE DEPTH	200	CY	
56		1050-0130	FABRICATED STRUCTURAL STEEL REPAIR GALVANIZED	5785	LB	
57		1050-0131	FABRICATED STRUCTURAL STEEL REPAIR GALVANIZED	1275	LB	
58		5070-0200	PAINTING EXISTING STRUCTURAL STEEL (MODIFIED)	1	LS	
59		5070-0201	PAINTING EXISTING STRUCTURAL STEEL (MODIFIED)	1	LS	
60		1072-0100	CONTAINMENT	1	LS	
61		1072-0101	CONTAINMENT	1	LS	
62		1072-0200	WASTE MANAGEMENT	1	LS	
63		1072-0300	WORKER HEALTH AND SAFETY	1	LS	
64		1090-1006	STANDARD EXPANSION DAM REPLACEMENT 3" MOVEMENT	47	LF	
65		1090-1008	STANDARD EXPANSION DAM REPLACEMENT 4" MOVEMENT	141	LF	
66		1999-0000	TRAINEES FOR PROJECTS 100% STATE FUNDED	1000	HR	
67		9000-0060	REPLACE BEARING ABUTMENT 1	6	EA	
68		9000-0061	REPLACE BEARING PIER 2 SPAN 2	6	EA	
69		9000-0062	REPLACE BEARING PIER 2 SPAN 3	6	EA	
70		9000-0063	REPLACE BEARING ABUTMENT 2	6	EA	
71		9000-0080	ULTRASONIC TESTING OF PINS	12	EA	
72		9000-0100	JACKING BRIDGE SUPERSTRUCTURE	1	LS	
73		9000-0105	SILICONE JOINT SEALING MATERIAL	686	LF	
74		9000-0110	CLEAN DRAINAGE SYSTEM	1	LS	
75		9000-0120	SPECIAL MORTAR REPAIR	10	SF	
76		9000-0130	SPECIAL CONCRETE REPAIR	292	SF	
77		9000-0135	SCARIFICATION 1 1/2" DEPTH	3572	SY	
78		9000-0160	SIDEWALK FRONT EDGE REPAIR	256	LF	
79		9000-0165	BRIDGE UTILITY ACCESS REMOVAL AND CONCRETE DECK REPAIR	1	LS	
80		9000-0170	BARRIER CAP AT APPROACH	1	LS	
81		9000-0175	BARRIER RAILING BOLT REPLACEMENT	50	EA	
82		9000-0180	REMOVE TACK WELD AT FIELD SPLICE	1056	EA	
83		9000-0185	REMOVE DETERIORATED PORTION OF GIRDER STIFFENER	4	EA	
84		9000-0190	FILL EXISTING HOLE IN FLANG WITH NEW H.S. BOLT	96	EA	
85		9000-0195	REPLACE EXISTING BOLT WITH NEW H.S. BOLT	500	EA	
86		9000-0200	UNFORESEEN BRIDGE REPAIRS	1	LS	
87		9000-0300	TEMPORARY RAILROAD CROSSING	1	LS	
88		9000-0500	COVID-19 SAFETY PLAN SIGN	2	EA	