

**BID DATE: 02/11/2021  
KINSLEY NO. 213008**

Line No.	Alt Code	Item No.	Short Description	QTY	Unit	Unit Price
1		0201-0001	CLEARING AND GRUBBING	1	LS	
2		0203-0001	CLASS 1 EXCAVATION	2220	CY	
3		0203-0006	SAW CUTTING	1750	LF	
4		0204-0100	CLASS 3 EXCAVATION	10	CY	
5		4205-0266	SELECTED BORROW EXCAVATION ROCK CLASS R-6 ( VOIDS FILLED WITH CONCRETE & CHOKED WITH NATURAL STREAMBED MATERIAL)	32	CY	
6		0205-0292	STRUCTURE BACKFILL	404	CY	
7		0212-0001	GEOTEXTILE CLASS 1	705	LF	
8		0212-0014	GEOTEXTILE CLASS 4 TYPE A	2699	SY	
9		0313-0420	SUPERPAVE ASPHALT MIXTURE DESIGN BASE COURSE PG 64S-22 0.3 TO < 3 MILLION ESALS 25.0 MM MIX 3" DEPTH	1707	SY	
10		0350-0106	SUBBASE 6" DEPTH (NO. 2A)	1949	SY	
11		0413-0246	SUPERPAVE ASPHALT MIXTURE DESIGN WEARING COURSE PG 64S-22 0.3 TO < 3 MILLION ESALS 9.5 MM MIX 1 1/2" DEPTH SRL-G	3177	SY	
12		0413-1022	SUPERPAVE ASPHALT MIXTURE DESIGN WEARING COURSE (SCRATCH) PG 64S-22 0.3 TO < 3 MILLION ESALS 9.5 MM MIX SRL-G	2	TON	
13		0413-2072	SUPERPAVE ASPHALT MIXTURE DESIGN WEARING COURSE (LEVELING) PG 64S-22 0.3 TO < 3 MILLION ESALS 9.5 MM MIX SRL-G	40	TON	
14		0413-6045	SUPERPAVE ASPHALT MIXTURE DESIGN BINDER COURSE PG 64S-22 0.3 TO < 3 MILLION ESALS 19.0 MM MIX 2 1/2" DEPTH	1548	SY	
15		0460-0001	ASPHALT TACK COAT	5094	SY	
16		0461-0001	ASPHALT PRIME COAT	122	SY	
17		0491-0019	MILLING OF ASPHALT PAVEMENT SURFACE VARIABLE DEPTH MILLED MATERIAL RETAINED BY CONTRACTOR	1470	SY	
18		0608-0001	MOBILIZATION	1	LS	
19		0609-0007	INSPECTOR'S FIELD OFFICE AND INSPECTION FACILITIES TYPE B	1	LS	
20		0609-0009	EQUIPMENT PACKAGE	1	LS	
21		0610-7002	6" PAVEMENT BASE DRAIN	705	LF	
22		0615-0022	6" SUBSURFACE DRAIN OUTLETS	30	LF	
23		0619-0459	PERM. IMPACT ATTENUATING DEVICE TYPE II TEST LEVEL 3 TANGENT (MASH)	4	EA	
24		0620-0400	TERMINAL SECTION SINGLE	1	EA	
25		0620-0503	REMOVE EXISTING GUIDE RAIL (CONTRACTOR'S PROPERTY)	1058	LF	
26		0620-0872	BURIED-IN-BACKSLOPE TERMINAL SINGLE PANEL	1	EA	
27		0620-1600	TYPE 31-S GUIDE RAIL	425	LF	
28		0620-1602	TYPE 31-S GUIDE RAIL WITH 8' EXTRA LENGTH POSTS	375	LF	
29		0620-1645	CURVED W-BEAM GUIDE RAIL AT INTERSECTIONS	25	LF	
30		0620-1670	TYPE 31-STRONG POST IN-LINE ANCHOR	1	EA	
31		0626-0020	CORROSION RESISTANT GABIONS TYPE A	138	CY	
32		0686-0050	CONSTRUCTION SURVEYING TYPE D	1	LS	
33		0689-0003	CPM SCHEDULE	1	LS	
34		0690-0001	INTERNAL FACILITATION	2000	DOL	1
35		0703-0022	NO. 8 COARSE AGGREGATE	10	CY	
36		0802-0001	TOPSOIL FURNISHED AND PLACED	235	CY	
37		0804-0001	SEEDING AND SOIL SUPPLEMENTS - FORMULA B INCLUDING MULCH	10	LB	
38		0804-0003	SEEDING AND SOIL SUPPLEMENTS - FORMULA D INCLUDING MULCH	10	LB	
39		0804-0004	SEEDING - FORMULA E INCLUDING MULCH	30	LB	
40		0804-0005	SEEDING AND SOIL SUPPLEMENTS - FORMULA N INCLUDING MULCH	55	LB	
41		0804-0007	SEEDING AND SOIL SUPPLEMENTS - FORMULA W INCLUDING MULCH	5	LB	
42		0806-0113	TEMPORARY SHORT-TERM ROLLED EROSION CONTROL PRODUCT TYPE 2D	607	SY	
43		0810-0052	SELECTIVE TREE REMOVAL	43	EA	
44		0811-0003	TEMPORARY PROTECTIVE FENCE	705	LF	
45		0845-0001	UNFORESEEN WATER POLLUTION CONTROL	5000	DOL	1
46		0850-0031	ROCK CLASS R-3	337	CY	
47		0850-0034	ROCK CLASS R-6	23	CY	
48		0855-0003	PUMPED WATER FILTER BAG	1	EA	
49		0855-0004	REPLACEMENT PUMPED WATER FILTER BAG	1	EA	
50		4856-0001	REMOVAL SEDIMENT AND ROCK BARRIER (WITH COMPOST)	1	EA	

**BID DATE: 02/11/2021  
KINSLEY NO. 213008**

Line No.	Alt Code	Item No.	Short Description	QTY	Unit	Unit Price
51		0860-0000	INLET FILTER BAG FOR TYPE M INLET	1	EA	
52		0867-0012	COMPOST FILTER SOCK 12" DIAMETER	199	LF	
53		0867-0022	COMPOST FILTER SOCK 24" DIAMETER	877	LF	
54		0901-0001	MAINTENANCE AND PROTECTION OF TRAFFIC DURING CONSTRUCTION	1	LS	
55		0901-0240	ADDITIONAL TRAFFIC CONTROL SIGNS	250	SF	
56		0901-0320	4" STANDARD PAVEMENT MARKINGS PAINT & BEADS YELLOW	2000	LF	
57		0901-0330	4" STANDARD PAVEMENT MARKINGS PAINT & BEADS WHITE	2000	LF	
58		0901-0451	3-LINE CHANGEABLE MESSAGE SIGN WITHOUT TELECOMMUNICATIONS	4	EA	
59		0931-0001	POST MOUNTED SIGNS TYPE B	45	SF	
60		0935-0001	POST MOUNTED SIGNS TYPE F	45	SF	
61		0937-0339	FLEXIBLE DELINEATOR POST GROUND-MOUNT TYPE GM-2 RED POST WITH WHITE/BLANK SHEETING	2	EA	
62		0941-0001	RESET POST MOUNTED SIGNS TYPE B	1	EA	
63		0960-0140	WHITE HOT THERMOPLASTIC PAVEMENT LEGEND SLOW CURVE ARROW LEFT (INCLUDES ARROW THE WORD SLOW AND 2 TRANSVERSE BANDS)	1	EA	
64		0960-0141	WHITE HOT THERMOPLASTIC PAVEMENT LEGEND SLOW CURVE ARROW RIGHT (INCLUDES ARROW THE WORD SLOW AND 2 TRANSVERSE BANDS)	1	EA	
65		0962-1000	4" WHITE WATERBORNE PAVEMENT MARKINGS	2000	LF	
66		0962-1005	4" YELLOW WATERBORNE PAVEMENT MARKINGS	2000	LF	
67		1018-0001	REMOVAL OF EXISTING BRIDGE	1	LS	
<b>68</b>	<b>10</b>	<b>8510-0001</b>	<b>PRECAST CONCRETE BOX CULVERT AS DESIGNED S-37576</b>	<b>1</b>	<b>LS</b>	
		0204-0100	CLASS 3 EXCAVATION	221	CY	
		0205-0292	STRUCTURE BACKFILL	130	CY	
		0212-0014	GEOTEXTILE CLASS 4 TYPE A	257	SY	
		4220-0010	FLOWABLE BACKFILL TYPE B OR COMPACTED NO. 2A AGGREGATE BACKFILL	41	CY	
		0680-0121	MEMBRANE WATERPROOFING SYSTEM INSTALLED ON OTHER SURFACES	68	SY	
		0703-0022	NO. 8 COARSE AGGREGATE	54	CY	
		0703-0025	NO. 57 COARSE AGGREGATE	6	CY	
		1001-1080	CLASS AA CEMENT CONCRETE	4	CY	
		1085-0630	8' X 8' PRECAST REINFORCED CONCRETE BOX CULVERT SEGMENTS	80	LF	
			PRECAST REINFORCED CONCRETE INLET	1	EA	
			PRECAST REINFORCED CONCRETE OUTLET	1	EA	
69	10	1002-0053	REINFORCEMENT BARS EPOXY COATED	675	LB	
70	11	8510-0002	ALTERNATE PRECAST CONCRETE BOX CULVERT	1	LS	
71		9000-0001	TEMPORARY SANDBAG STREAM DIVERSION	1	LS	
72		9000-0002	TEMPORARY SANDBAG DIVERSION DAM	1	LS	
73		9000-0003	SUMP PIT	1	EA	
74		9000-0004	GEOGRID BANK STABILIZATION	45	LF	
75		9000-0005	STREAMBED MATERIAL	19	CY	
76		9000-0006	RELOCATE EXISTING MAILBOX	1	EA	
77		9000-0007	COVID-19 SAFETY PLAN SIGN	2	EA	
78		9000-0008	SPILL PREVENTION CONTROL & COUNTERMEASURE PLAN	1	LS	