

**BID DATE: 05/05/2021  
KINSLEY NO. 213005**

Line No.	Alt Code	Item No.	Short Description	QTY	Unit	Unit Price
100		0201-	CLEARING AND GRUBBING	1	LS	
200		0203-	CLASS 1 EXCAVATION	260	CY	
300		0203-	CLASS 1A EXCAVATION	13	CY	
400		0205-	FOREIGN BORROW EXCAVATION	380	CY	
500		0350-	SUBBASE (NO. 2A)	131	TON	
600		0413- 0344	SUPERPAVE ASPHALT MIXTURE DESIGN WEARING COURSE PG 64S-22 10 TO < 30 MILLION ESALS 12.5 MM MIX SRL-G	2420	TON	
700		0413- 6067	SUPERPAVE ASPHALT MIXTURE DESIGN BINDER COURSE PG 64S-22 10 TO < 30 MILLION ESALS 19.0 MM MIX	457	TON	
800		0460-	ASPHALT TACK COAT	22000	SY	
900		0469-	ASPHALT JOINT AND CRACK SEALING FOR ASPHALT SURFACES	5000	LF	
1000		2499-	PAYMENT ADJUSTMENT FOR ASPHALT MATERIALS	1	PDA	10000
1100		0501-	PLAIN CEMENT CONCRETE PAVEMENT 6" DEPTH	22	SY	
1200	10	0601-	18" THERMOPLASTIC PIPE GROUP VI 15'-2' FILL SHORE/TRENCH BOX	806	LF	
1300	11	0601-	18" REINFORCED CONCRETE PIPE TYPE B 7'- 3' FILL SHORE/TRENCH BOX	806	LF	
1400	20	0601-	24" THERMOPLASTIC PIPE GROUP VI 15'-2' FILL SHORE/TRENCH BOX	65	LF	
1500	21	0601-	24" REINFORCED CONCRETE PIPE TYPE B 15' - 3' FILL SHORE/TRENCH BOX	65	LF	
1600	30	0604-	18" PERFORATED THERMOPLASTIC PIPE GROUP VI 15'-2' FILL SHORE/TRENCH BOX	704	LF	
1700	31	0604-	18" REINFORCED CONCRETE PIPE TYPE B (OPEN JT) 7' - 3' FILL SHORE/TRENCH BOX	704	LF	
1800		0605-	TYPE M CONCRETE TOP UNIT AND GRATE	20	SET	
1900		0605-	STANDARD INLET BOX HEIGHT < /= 10'	15	EA	
2000		0605-	STANDARD INLET BOX HEIGHT > 10' AND < /= 20'	1	EA	
2100		0605-	TYPE 4 INLET BOX HEIGHT < /= 10'	4	EA	
2200		0608-	MOBILIZATION	1	LS	
2300		2609-	INSPECTOR'S FIELD OFFICE AND INSPECTION FACILITIES TYPE B	1	LS	
2400		3630-	PLAIN CEMENT CONCRETE CURB (6" REVEAL)	838	LF	
2500		0676-	CEMENT CONCRETE SIDEWALK	95	SY	
2600		0686-	CONSTRUCTION SURVEYING TYPE A	1	LS	
2700		0695-	DETECTABLE WARNING SURFACE POLYMER COMPOSITE	40	SF	
2800		0802-	TOPSOIL FURNISHED AND PLACED	247	CY	
2900		0804-	SEEDING AND SOIL SUPPLEMENTS - FORMULA B INCLUDING MULCH	98	LB	
3000		0804-	SEEDING - FORMULA E INCLUDING MULCH	22	LB	
3100		0860-	INLET FILTER BAG FOR TYPE M INLET	20	EA	
3200		0867-	COMPOST FILTER SOCK 12" DIAMETER	253	LF	
3300		0901-	MAINTENANCE AND PROTECTION OF TRAFFIC DURING CONSTRUCTION	1	LS	
3400		0901-	3-LINE CHANGEABLE MESSAGE SIGN WITHOUT TELECOMMUNICATIONS	1	EA	
3500		4901-	COVID-19 SAFETY PLAN SIGNS	3	EA	
3600		0931-	POST MOUNTED SIGNS TYPE B	223.5	SF	
3700		4962-	WHITE WATERBORNE PAVEMENT LEGEND "STRAIGHT ARROW" 9'-6" LENGTH	38	EA	
3800		0962-	4" WHITE WATERBORNE PAVEMENT MARKINGS	13500	LF	
3900		0962-	12" WHITE WATERBORNE PAVEMENT MARKINGS	184	LF	
4000		0962-	4" YELLOW WATERBORNE PAVEMENT MARKINGS	420	LF	
4100		0962-	WHITE WATERBORNE PAVEMENT LEGEND "HANDICAP SYMBOL" 3'-3" X 2'-11"	18	EA	
4200		0971-	REMOVE POST MOUNTED SIGNS TYPE B	2	EA	
4300		4000-	ALUMINUM BUS SHELTER	1	EA	
4400		4000-	PLUG EXISTING PIPE	16	EA	
4500		4000-	SHOULDER BACKUP	530	SY	
4600		4000-	8" UNDERDRAIN SYSTEM WITH 6" DOWNSPOUT CONNECTIONS	1320	LF	
4700		4000-	WHITE TRAFFIC ZONE PAINT LEGEND "BUS ONLY" 8'-0" HIGH LETTERS	1	EA	
4800		4000- 0007	WHITE WATERBORNE PAVEMENT LEGEND FOR DESIGNATED PARKING STALLS 1'-0" HIGH LETTERS	24	EA	
4900		4000-	COMPOST SOCK WASHOUT	1	EA	

**E-ZPASS CUSTOMER SERVICE CENTER SITE  
IMPROVEMENTS IN DAUPHIN COUNTY (VERSION 2)**

**BID ITEMS**