

**BID DATE: 06/03/2021
KINSLEY NO. 213064**

Line No.	Alt Code	Item No.	Short Description	QTY	Unit	Unit Price
1		2030001	CLASS 1 EXCAVATION	400	CY	
2		2120014	GEOTEXTILE, CLASS 4, TYPE A	265	SY	
3		3500105	SUBBASE 5" DEPTH (NO. 2A)	545	SY	
4		3500107	SUBBASE 7" DEPTH (NO. 2A)	230	SY	
5		7030020	NO.1 COARSE AGGREGATE	50	CY	
6		8060143	ROLLED EROSION CONTROL PRODUCT	95	SY	
7		8500021	ROCK, CLASS R3	30	SY	
8		8670018	COMPOST FILTER SOCK, 18" DIAMETER	110	LF	
9		80000001	BRIDGE CONSTRUCTION, AS DESIGNED	1	LS	
			PREFORMED NEOPRENE COMPRESSION JOINT SEAL, 1 1/2" MOVEM	22	LF	
			PREFORMED NEOPRENE COMPRESSION JOINT SEAL, 2" MOVEMEN	22	LF	
			SHEAR CONNECTOR	156	EA	
			FABRICATED STRUCTURAL STEEL	112130	LBS	
			PRECAST REINFORCED CONCRETE DECK PANELS	106	LF	
			LAMINATED NEOPRENE BEARING PAD	6	EA	
			STRUCTURE MOUNTED RAILING	212	LF	
10		80000002	BRIDGE REDECKING, AS DESIGNED	1	LS	
			PREFORMED NEOPRENE COMPRESSION JOINT SEAL, 1 1/2" MOVEM	176	LF	
			SHEAR CONNECTOR	960	EA	
			PRECAST REINFORCED CONCRETE DECK PANELS	484	LF	
			STRUCTURE MOUNTED RAILING	968	LF	
11	Option	80000003	BRIDGE REDECKING, ALTERNATE	1	LS	
12		90000001	TEMPORARY GIRDER BRACING	1	LS	
13		90000002	TRUSS TOP CHORD REPAIR	200	EA	
14		90000003	TRUSS SUPPLEMENTAL WIND BRACING	1	LS	
15		90000004	FABRICATED STRUCTURAL STEEL, REPAIRS	1,550	LB	
16		90000005	BOLT AND RIVET REPLACEMENT	55	EA	
17		90000006	CLEAN COLUMN BASES	20	EA	
18		90000007	CORROSION ARRESTING PAINT SYSTEM COLUMN BASES	20	EA	
19		90000008	BRIDGE INSPECTION WALKWAY	1	LS	
20		92000001	BRIDGE PREPARATION	1	LS	
21		93000001	INSPECTION ACCESS DURING CONSTRUCTION	1	LS	
22		90560001	UNFORESEEN STRUCTURAL STEEL REPAIR	125,000	DOL	
23		96670022	SELECTED MATERIAL SURFACING, 2 INCH DEPTH (LIMESTONE)	545	SY	
24		99000001	APPROACH RAILING	145	LF	

**MARTIC TOWNSHIP LANCASTER COUNTY
MARTIC FORGE VIADUCT BRIDGE REPLACEMENT
BID ITEMS**