

**BID DATE: 06/10/2021
KINSLEY NO. 213062**

Line No.	Alt Code	Item No.	Short Description	QTY	Unit	Unit Price
1		0413-0383	SP WEARING PG64E-22 0.3TO<3 MILLION ESALS 9.5MM 1 1/2" DEPTH SRL-H	40459	SY	
2		0413-0388	SP WEARING PG64E-22 3TO<10 MILLION ESALS 12.5MM 2" DEPTH SRL-H	27820	SY	
3		0413-1024	SP WEARING (SCRATCH) PG 64S-22 0.3TO<3 MILLION ESALS 9.5MM SRL-L	2639	TON	
4		0413-2074	SP WEARING (LEVELING) PG 64S-22 0.3TO<3 MILLION ESALS 9.5MM SRL-L	207	TON	
5		0413-9999	PERCENT WITHIN LIMITS (PWL) LOT INCENTIVE/DISINCENTIVE	21924	DOL	1
6		0450-3410	SP BINDER MANUAL PATCHING PG64S-22 0.3TO<3 MILLION ESALS 19.0MM	344	TON	
7		0460-0001	ASPHALT TACK COAT	106444	SY	
8		0460-0003	ASPHALT TACK COAT (NTT/CNTT)	30114	SY	
9		0491-0012	MILLING OF ASPHALT PAVEMENT 1 1/2" DEPTH MILLED MATERIAL RETAINED BY CONTRACTOR	38165	SY	
10		0491-0019	MILLING OF ASPHALT PAVEMENT VARIABLE DEPTH MILLED MATERIAL RETAINED BY CONTRACTOR	30114	SY	
11		0512-0001	LONGITUDINAL JOINT CLEANING AND SEALING	16703	LF	
12		0515-0001	SAWING AND SEALING OF ASPHALT OVERLAYS	11144	LF	
13		0516-1008	ACCELERATED CONCRETE PAVEMENT PATCHING, PERPENDICULAR JOINTS, TYPE A, 8" DEPTH	115	SY	
14		0516-1009	ACCELERATED CONCRETE PAVEMENT PATCHING, PERPENDICULAR JOINTS, TYPE A, 9" DEPTH	1113	SY	
15		0516-1108	ACCELERATED CONCRETE PAVEMENT PATCHING, PERPENDICULAR JOINTS, TYPE B, 8" DEPTH	23	SY	
16		0516-1109	ACCELERATED CONCRETE PAVEMENT PATCHING, PERPENDICULAR JOINTS, TYPE B, 9" DEPTH	279	SY	
17		0516-2007	PATCHING JOINT	2029	LF	
18		0516-2008	NEW PAVEMENT JOINT	345	LF	
19		0521-0001	TRANSVERSE JOINT CLEANING AND SEALING	8770	LF	
20		0608-0001	MOBILIZATION	1	LS	
21		0609-0003	INSPECTOR'S FIELD OFFICE AND INSPECTION FACILITIES, TYPE B	1	LS	
22		0609-0009	EQUIPMENT PACKAGE	1	LS	
23		0630-0010	PLAIN CEMENT CONCRETE CURB, INCLUDING REMOVAL OF EXISTING CURB	2545	LF	
24		0676-0001	CEMENT CONCRETE SIDEWALK	2387	SY	
25		0686-0040	CONSTRUCTION SURVEYING, TYPE C	1	LS	
26		0689-0001	NARRATIVE SCHEDULE	1	LS	
27		0690-0001	INTERNAL FACILITATION	1000	DOL	1
28	10	0695-0004	DETECTABLE WARNING SURFACE, POLYMER COMPOSITE	1288	SF	
29	11	0695-0002	DETECTABLE WARNING SURFACE, CAST IRON	1288	SF	
30	12	0695-0003	DETECTABLE WARNING SURFACE, POLYMER CONCRETE	1288	SF	
31		0901-0001	MAINTENANCE AND PROTECTION OF TRAFFIC DURING CONSTRUCTION	1	LS	
32		0960-0005	6" WHITE HOT THERMOPLASTIC PAVEMENT MARKINGS	6652	LF	
33		0960-0021	24" WHITE HOT THERMOPLASTIC PAVEMENT MARKINGS	1193	LF	
34		0960-0101	WHITE HOT THERMOPLASTIC LEGEND, "ONLY", 8' - 0"	49	EA	
35		0960-0220	WHITE HOT THERMOPLASTIC LEGEND, "STRAIGHT ARROW", 12' - 0" X 1' - 8"	2	EA	
36		0960-0222	WHITE HOT THERMOPLASTIC LEGEND, "RIGHT ARROW", 12' - 0" X 3' - 0"	3	EA	
37		0960-0224	WHITE HOT THERMOPLASTIC LEGEND, "LEFT ARROW", 12' - 0" X 3' - 0"	44	EA	
38		0962-1000	4" WHITE WATERBORNE PAVEMENT MARKINGS	33412	LF	
39		0962-1005	4" YELLOW WATERBORNE PAVEMENT MARKINGS	46860	LF	
40		9000-0001	DESIGN OF CONCRETE CURB RAMPS [BY QUADRANT]	88	EA	
41		9000-0002	COVID-19 SAFETY PLAN SIGN	1	EA	
42		9000-0003	HAMBURG WHEEL TRACK AND CRACKING TOLERANCE INDEX TESTING	4500	DOL	1