

**BID DATE: 10/07/2021
KINSLEY NO. 213116**

Line No.	Alt Code	Item No.	Short Description	QTY	Unit	Unit Price
1		0201-0001	CLEARING AND GRUBBING	1	LS	
2		0203-0001	CLASS 1 EXCAVATION	214	CY	
3		0212-0014	GEOTEXTILE CLASS 4 TYPE A	330	SY	
4		0313-0320	SUPERPAVE ASPHALT MIXTURE DESIGN BASE COURSE PG 64S-22 < 0.3 MILLION ESALs 25.0 MM MIX 3" DEPTH	320	SY	
5		0350-0106	SUBBASE 6" DEPTH (NO. 2A)	496	SY	
6		0350-0208	SUBBASE 8" DEPTH (NO. OGS)	428	SY	
7		0413-0199	SUPERPAVE ASPHALT MIXTURE DESIGN WEARING COURSE PG 64S-22 < 0.3 MILLION ESALS 9.5 MM MIX 2" DEPTH SRL-M	624	SY	
8		0413-6035	SUPERPAVE ASPHALT MIXTURE DESIGN BINDER COURSE PG 64S-22 < 0.3 MILLION ESALS 19.0 MM MIX 2 1/2" DEPTH	320	SY	
9		0460-0001	ASPHALT TACK COAT	1093	SY	
10		0461-0001	ASPHALT PRIME COAT	772	SY	
11		0491-0019	MILLING OF ASPHALT PAVEMENT SURFACE VARIABLE DEPTH MILLED MATERIAL RETAINED BY CONTRACTOR	396	SY	
12	10	0601-7313	18" REINFORCED CONCRETE PIPE TYPE B 15' - 1.5' FILL	52	LF	
13	11	0601-0763	18" DUCTILE IRON PIPE	52	LF	
14		0605-2600	TYPE D ENDWALL	1	EA	
15		0605-2731	TYPE M CONCRETE TOP UNIT AND BICYCLE SAFE GRATE	3	SET	
16		0605-2850	STANDARD INLET BOX HEIGHT < / = 10'	3	EA	
17		0608-0001	MOBILIZATION	1	LS	
18		0609-0007	INSPECTOR'S FIELD OFFICE AND INSPECTION FACILITIES TYPE B	1	LS	
19		0609-0009	EQUIPMENT PACKAGE	1	LS	
20		4619-0459	PERMANENT IMPACT ATTENUATING DEVICE TYPE II TEST LEVEL 3 TANGENT (MASH) (- BROWN)	5	EA	
21		4620-0012	THRIE-BEAM TO PA TYPE 10M BRIDGE BARRIER TRANSITION WITHOUT INLET PLACEMENT (- BROWN)	2	EA	
22		4620-0013	THRIE-BEAM TO PA TYPE 10M BRIDGE BARRIER TRANSITION WITH INLET PLACEMENT (BROWN)	2	EA	
23		4620-0400	TERMINAL SECTION SINGLE (- BROWN)	1	EA	
24		0620-0503	REMOVE EXISTING GUIDE RAIL (CONTRACTOR'S PROPERTY)	1553	LF	
25		4620-1602	TYPE 31-S GUIDE RAIL WITH 8' EXTRA LENGTH POSTS (- BROWN)	1333	LF	
26		4620-1670	TYPE 31-STRONG POST IN-LINE ANCHOR (- BROWN)	7	EA	
27		0686-0010	CONSTRUCTION SURVEYING TYPE A	1	LS	
28		0689-0003	CPM SCHEDULE	1	LS	
29		0690-0001	INTERNAL FACILITATION	1000	DOL	1
30		0804-0011	SEEDING AND SOIL SUPPLEMENTS - FORMULA B	42	LB	
31		0804-0014	SEEDING - FORMULA E	19	LB	
32		0804-0020	SEEDING AND SOIL SUPPLEMENTS - FORMULA L	44	LB	
33		0805-0021	MULCHING - HAY	1	TON	
34		0806-0113	TEMPORARY SHORT-TERM ROLLED EROSION CONTROL PRODUCT TYPE 2D	618	SY	
35		0811-0003	TEMPORARY PROTECTIVE FENCE	372	LF	
36		0845-0001	UNFORESEEN WATER POLLUTION CONTROL	1000	DOL	1
37		0849-0010	ROCK CONSTRUCTION ENTRANCE	2	EA	
38		4850-0021	ROCK CLASS R-3 (MODIFIED)	4	SY	
39		4850-0022	ROCK CLASS R-4 (MODIFIED)	20	SY	
40		4850-0035	ROCK CLASS R-7 (CHOKED WITH ROCK CLASS R-4)	140	CY	
41		0855-0003	PUMPED WATER FILTER BAG	1	EA	
42		0855-0004	REPLACEMENT PUMPED WATER FILTER BAG	1	EA	
43		0860-0000	INLET FILTER BAG FOR TYPE M INLET	3	EA	
44		0867-0018	COMPOST FILTER SOCK 18" DIAMETER	1372	LF	
45		0901-0001	MAINTENANCE AND PROTECTION OF TRAFFIC DURING CONSTRUCTION	1	LS	
46		0901-0231	ADDITIONAL WARNING LIGHTS TYPE B	100	DAY	
47		0901-0240	ADDITIONAL TRAFFIC CONTROL SIGNS	100	SF	
48		0901-0320	4" STANDARD PAVEMENT MARKINGS PAINT & BEADS YELLOW	1760	LF	
49		0901-0330	4" STANDARD PAVEMENT MARKINGS PAINT & BEADS WHITE	1760	LF	
50		0931-0001	POST MOUNTED SIGNS TYPE B	6	SF	

PENNDOT SR 3005-001 ADAMS COUNTY

BID ITEMS

PENNDOT PROJECT NO. 78662

PAGE 1 OF 2

BID DATE: 10/07/2021
KINSLEY NO. 213116

Line No.	Alt Code	Item No.	Short Description	QTY	Unit	Unit Price
51		0941-0001	RESET POST MOUNTED SIGNS TYPE B	1	EA	
52		0962-1000	4" WHITE WATERBORNE PAVEMENT MARKINGS	1760	LF	
53		0962-1005	4" YELLOW WATERBORNE PAVEMENT MARKINGS	1760	LF	
54		0971-0001	REMOVE POST MOUNTED SIGNS TYPE B	6	EA	
55		1001-0980	MECHANICAL TEXTURING WITH LONGITUDINAL SAWED GROOVES	240	SY	
56		1018-0050	REMOVAL OF PORTION OF EXISTING BRIDGE	1	LS	
57	20	8010-0001	BRIDGE STRUCTURE AS DESIGNED S-39282	1	LS	
		0204-0100	CLASS 3 EXCAVATION	40	CY	
		0205-0292	STRUCTURE BACKFILL	30	CY	
		0680-0121	MEMBRANE WATERPROOFING SYSTEM INSTALLED ON OTHER SURFACES	104	SY	
		0703-0025	NO. 57 COARSE AGGREGATE	12	CY	
		1001-0611	6" STRUCTURE FOUNDATION DRAIN	70	LF	
		1001-1000	CLASS AAAP CEMENT CONCRETE	68	CY	
		1001-1080	CLASS AA CEMENT CONCRETE	18	CY	
		1001-1120	CLASS A CEMENT CONCRETE	9	CY	
		1080-0405	PRESTRESSED CONCRETE SPREAD BOX BEAMS, 36" X 27"	358	LF	
		1019-0050	PROTECTIVE COATING FOR REINFORCED CONCRETE SURFACES (PENETRATING SEALERS, BRIDGE SUPERSTRUCTURE)	290	SY	
		5088-0001	PA TYPE 10M BRIDGE BARRIER RAILING - BROWN	143	LF	
			6" PVC PIPE (SCHEDULE 40)	30	LF	
58	20	1002-0053	REINFORCEMENT BARS EPOXY COATED	15700	LB	
59	21	8100-0001	STEEL BRIDGE STRUCTURE	1	LS	
60	22	8000-0001	PRESTRESSED CONCRETE BRIDGE STRUCTURE	1	LS	
61		9000-0001	VIDEO LOG OF NPS ROAD	1	LS	
62		9000-0002	REPAIR OF NPS ROADS	25000	DOL	1