

**BID DATE: 10/07/2021
KINSLEY NO. 213115**

Line No.	Alt Code	Item No.	Short Description	QTY	Unit	Unit Price
1		0201-0001	CLEARING AND GRUBBING	1	LS	
2		0203-0001	CLASS 1 EXCAVATION	460	CY	
3		0212-0001	GEOTEXTILE CLASS 1	115	LF	
4		0212-0014	GEOTEXTILE CLASS 4 TYPE A	690	SY	
5		0313-0326	SUPERPAVE ASPHALT MIXTURE DESIGN BASE COURSE PG 64S-22 < 0.3 MILLION ESALS 25.0 MM MIX 6" DEPTH	688	SY	
6		0350-0106	SUBBASE 6" DEPTH (NO. 2A)	766	SY	
7		0413-0194	SUPERPAVE ASPHALT MIXTURE DESIGN WEARING COURSE PG 64S-22 < 0.3 MILLION ESALS 9.5 MM MIX 1 1/2" DEPTH SRL-M	1225	SY	
8		0413-6036	SUPERPAVE ASPHALT MIXTURE DESIGN BINDER COURSE PG 64S-22 < 0.3 MILLION ESALS 19.0 MM MIX 3" DEPTH	688	SY	
9		0460-0001	ASPHALT TACK COAT	1912	SY	
10		0461-0001	ASPHALT PRIME COAT	97	SY	
11		0491-0019	MILLING OF ASPHALT PAVEMENT SURFACE VARIABLE DEPTH MILLED MATERIAL RETAINED BY CONTRACTOR	380	SY	
12	10	0601-7313	18" REINFORCED CONCRETE PIPE TYPE B 15' - 1.5' FILL	68	LF	
13	11	0601-0353	18" THERMOPLASTIC PIPE GROUP III 8'-2' FILL	68	LF	
14	12	0601-0763	18" DUCTILE IRON PIPE	68	LF	
15	20	0604-7313	18" REINFORCED CONCRETE PIPE TYPE B (OPEN JOINT) 15' - 1.5' FILL	115	LF	
16	21	0604-0400	18" PERFORATED THERMOPLASTIC PIPE GROUP VI 15'-2' FILL	115	LF	
17	22	0604-2843	18" PERFORATED CORRUGATED ALUMINUM ALLOY PIPE TYPE I (2 2/3" X 1/2" CORRUGATIONS) 14 GAGE	115	LF	
18		0605-2600	TYPE D ENDWALL	1	EA	
19		0605-2731	TYPE M CONCRETE TOP UNIT AND BICYCLE SAFE GRATE	7	SET	
20		0605-2850	STANDARD INLET BOX HEIGHT < /= 10'	7	EA	
21		0608-0001	MOBILIZATION	1	LS	
22		0609-0003	INSPECTOR'S FIELD OFFICE AND INSPECTION FACILITIES TYPE B	1	LS	
23		0609-0009	EQUIPMENT PACKAGE	1	LS	
24		4619-0459	PERMANENT IMPACT ATTENUATING DEVICE TYPE II TEST LEVEL 3 TANGENT (MASH) (- BROWN)	2	EA	
25		4620-0400	TERMINAL SECTION SINGLE (- BROWN)	2	EA	
26		0620-0503	REMOVE EXISTING GUIDE RAIL (CONTRACTOR'S PROPERTY)	284	LF	
27		4620-1602	TYPE 31-S GUIDE RAIL WITH 8' EXTRA LENGTH POSTS (- BROWN)	248	LF	
28		4620-1670	TYPE 31-STRONG POST IN-LINE ANCHOR (- BROWN)	2	EA	
29		0630-0001	PLAIN CEMENT CONCRETE CURB	8	LF	
30		4636-0001	ASPHALT CONCRETE CURB (MONOLITHIC)	143	LF	
31		0686-0010	CONSTRUCTION SURVEYING TYPE A	1	LS	
32		0689-0003	CPM SCHEDULE	1	LS	
33		0690-0001	INTERNAL FACILITATION	1000	DOL	1
34		0804-0011	SEEDING AND SOIL SUPPLEMENTS - FORMULA B	21	LB	
35		0804-0014	SEEDING - FORMULA E	10	LB	
36		0804-0020	SEEDING AND SOIL SUPPLEMENTS - FORMULA L	25	LB	
37		0805-0021	MULCHING - HAY	1	TON	
38		0806-0113	TEMPORARY SHORT-TERM ROLLED EROSION CONTROL PRODUCT TYPE 2D	278	SY	
39		0811-0003	TEMPORARY PROTECTIVE FENCE	389	LF	
40		0845-0001	UNFORESEEN WATER POLLUTION CONTROL	1000	DOL	1
41		0849-0010	ROCK CONSTRUCTION ENTRANCE	2	EA	
42		0850-0031	ROCK CLASS R-3	1	CY	
43		0855-0003	PUMPED WATER FILTER BAG	1	EA	
44		0855-0004	REPLACEMENT PUMPED WATER FILTER BAG	1	EA	
45		0860-0000	INLET FILTER BAG FOR TYPE M INLET	6	EA	
46		0867-0018	COMPOST FILTER SOCK 18" DIAMETER	802	LF	
47		0901-0001	MAINTENANCE AND PROTECTION OF TRAFFIC DURING CONSTRUCTION	1	LS	
48		0901-0231	ADDITIONAL WARNING LIGHTS TYPE B	100	DAY	
49		0901-0240	ADDITIONAL TRAFFIC CONTROL SIGNS	100	SF	
50		0901-0320	4" STANDARD PAVEMENT MARKINGS PAINT & BEADS YELLOW	800	LF	
51		0901-0330	4" STANDARD PAVEMENT MARKINGS PAINT & BEADS WHITE	800	LF	

PENNDOT SR 3073-003 YORK COUNTY

BID ITEMS

PENNDOT PROJECT NO. 78816

PAGE 1 OF 2

BID DATE: 10/07/2021
KINSLEY NO. 213115

Line No.	Alt Code	Item No.	Short Description	QTY	Unit	Unit Price
52		0931-0001	POST MOUNTED SIGNS TYPE B	18	SF	
53		0962-1000	4" WHITE WATERBORNE PAVEMENT MARKINGS	800	LF	
54		0962-1005	4" YELLOW WATERBORNE PAVEMENT MARKINGS	800	LF	
55		1001-0970	MECHANICAL TEXTURING WITH TRANSVERSE SAWED GROOVES	55	SY	
56		1018-0001	REMOVAL OF EXISTING BRIDGE	1	LS	
57	30	8510-0001	PRECAST REINFORCED CONCRETE BOX CULVERT AS DESIGNED S-39285	1	LS	
			16'-0" x 7'-6" PRECAST REINFORCED CONCRETE BOX CULVERT	33	LF	
			CLASS 3 EXCAVATION	700	CY	
			STRUCTURE BACKFILL	480	CY	
			STRUCTURE MOUNTED GUIDE RAIL - BROWN	103	LF	
			MEMBRANE WATERPROOFING SYSTEM INSTALLED ON OTHER SURFACES	70	SY	
			NO. 2A COARSE AGGREGATE	160	CY	
			NO. 57 COARSE AGGREGATE	5	CY	
			ROCK, CLASS R-6 CHOKED WITH NATURAL STREAMBED MATERIAL	81	CY	
			CLASS AA CEMENT CONCRETE	7	CY	
			CLASS A CEMENT CONCRETE, SULFATE RESISTANT	73	CY	
			CLASS AAAP CEMENT CONCRETE	13	CY	
		1019-0050	PROTECTIVE COATING FOR REINFORCED CONCRETE SURFACES (PENETRATING SEALERS, BRIDGE SUPERSTRUCTURE)	95	SY	
58	30	1002-0052	REINFORCEMENT BARS EPOXY COATED	8600	LB	
59	31	8510-0002	PRECAST REINFORCED CONCRETE BOX CULVERT WITH PRECAST WINGWALLS AND CUTOFF WALLS AS DESIGNED S-39285A	1	LS	
60	32	8510-0003	PRECAST REINFORCED CONCRETE BOX CULVERT S-39285A	1	LS	
61	40	8610-0001	CAST-IN-PLACE REINFORCED CONCRETE RETAINING WALL AS DESIGNED S-39513	1	LS	
		0204-0100	CLASS 3 EXCAVATION	370	CY	
		0205-0292	STRUCTURE BACKFILL	240	CY	
		4620-0595	STRUCTURE MOUNTED GUIDE RAIL - BROWN	90	LF	
		0680-0121	MEMBRANE WATERPROOFING SYSTEM INSTALLED ON OTHER SURFACES	45	SY	
		4850-0034	ROCK, CLASS R-6 CHOKED WITH NATURAL STREAMBED MATERIAL	70	CY	
		1001-1080	CLASS AA CEMENT CONCRETE	4	CY	
		5001-1120	CLASS A CEMENT CONCRETE , SULFATE RESISTANT	75	CY	
		1019-0050	PROTECTIVE COATING FOR REINFORCED CONCRETE SURFACES (PENETRATING SEALERS, BRIDGE SUPERSTRUCTURE)	30	SY	
62	40	1002-0053	REINFORCEMENT BARS EPOXY COATED	7600	LB	
63	41	8610-0002	CONCRETE RETAINING WALL	1	LS	
64	42	8620-0001	PREFABRICATED RETAINING WALL	1	LS	
65		9000-0001	VIDEO LOG OF TOWNSHIP ROADS	1	LS	
66		9000-0002	REPAIR OF TOWNSHIP ROADS	25000	DOL	1
67		9000-0003	TEMPORARY STREAM DIVERSION DEVICES	21	LF	
68		9000-0005	OVEREXCAVATION AND BACKFILLING UNDER FOUNDATION	19	CY	
69		9000-0006	TEMPORARY CHANNEL	140	LF	
70		9000-0007	TEMPORARY STREAM BYPASS SYSTEM	1	LS	
71		9000-5100	ELECTRONIC TICKETING SYSTEM	1	LS	
72		9203-0101	TEMPORARY EXCAVATION SUPPORT AND PROTECTION SYSTEM S-39285	1	LS	
73		9203-0102	TEMPORARY EXCAVATION SUPPORT AND PROTECTION SYSTEM S-39513	1	LS	