

**BID DATE: 01/27/2022
KINSLEY NO. 223006**

Line No.	Alt Code	Item No.	Short Description	QTY	Unit	Unit Price
1		0201-0001	CLEARING AND GRUBBING	1	LS	
2		0203-0001	CLASS 1 EXCAVATION	56	CY	
3		0204-0001	CLASS 2 EXCAVATION	12	CY	
4		0205-0364	SELECTED BORROW EXCAVATION ROCK CLASS R-4	133	TON	
5		0206-0010	SELECT GRANULAR MATERIAL (2RC)	1482	TON	
6		0212-0001	GEOTEXTILE CLASS 1	325	LF	
7		0212-0014	GEOTEXTILE CLASS 4 TYPE A	112	SY	
8		0404-0012	ASPHALT PAVEMENT RIDE QUALITY INCENTIVE SCHEDULE B	5360	DOL	1
9		0405-0001	ASPHALT PAVEMENT LONGITUDINAL JOINT DENSITY INCENTIVE/DISINCENTIVE	9368	DOL	1
10		0413-0258	SP WEARING PG64S-22 0.3TO<3 MILLION ESALS 9.5 MM MIX SRL-L	360	TON	
11		0413-1024	SP WEARING (SCRATCH) PG64S-22 0.3TO<3 MILLION ESALS 9.5 MM MIX SRL-L	4941	TON	
12		0413-3222	SP WEARING RPS PG64S-22 0.3TO<3 MILLION ESALS 12.5 MM MIX 2" DEPTH SRL-M	83145	SY	
13		0413-9999	PERCENT WITHIN LIMITS (PWL) LOT INCENTIVE/DISINCENTIVE	33258	DOL	1
14		0460-0001	ASPHALT TACK COAT	164642	SY	
15		0461-0002	ASPHALT PRIME COAT	4133	GAL	
16		0491-0014	MILLING OF ASPHALT PAVEMENT 2 1/2" DEPTH - CONTRACTOR'S MILLINGS	104	SY	
17		0491-0019	MILLING OF ASPHALT PAVEMENT VARIABLE DEPTH - CONTRACTOR'S MILLINGS	1034	SY	
18		0601-5901	CLEANING EXISTING PIPE CULVERTS DIAMETERS UP TO AND INCLUDING 36"	500	LF	
19		0601-7008	15" REINFORCED CONCRETE PIPE TYPE A 20' - 1.5' FILL	40	LF	
20		0605-1300	CLEANING DRAINAGE STRUCTURES	10	EA	
21		0605-2701	BICYCLE SAFE INLET GRATE	14	EA	
22		0605-2731	TYPE M CONCRETE TOP UNIT AND BICYCLE SAFE GRATE	1	SET	
23		0605-2850	STANDARD INLET BOX HEIGHT < / = 10'	1	EA	
24		0606-0050	GRADE ADJUSTMENT OF EXISTING INLETS	15	SET	
25		0608-0001	MOBILIZATION	1	LS	
26		0609-0007	INSPECTOR'S FIELD OFFICE AND INSPECTION FACILITIES TYPE B	1	LS	
27		0609-0009	EQUIPMENT PACKAGE	1	LS	
28		0610-1102	8" PIPE UNDERDRAIN TYPE II BACKFILL INCLUDING SHOULDER RESTORATION	325	LF	
29		0619-0470	PERMANENT IMPACT ATTENUATING DEVICE TYPE II TEST LEVEL 3 (ENERGY ABSORBING TERMINALS TANGENT)	21	EA	
30		0620-0015	THRIE-BEAM TO VERTICAL WALL BRIDGE BARRIER TRANSITION	4	EA	
31		0620-0503	REMOVE EXISTING GUIDE RAIL (CONTRACTOR'S PROPERTY)	3438	LF	
32		0620-0872	BURIED-IN-BACKSLOPE TERMINAL SINGLE PANEL	1	EA	
33		0620-0900	REMOVE CONCRETE ANCHORAGE	17	EA	
34		0620-1600	TYPE 31-S GUIDE RAIL	1575	LF	
35		0620-1625	TYPE 31-SC GUIDE RAIL	300	LF	
36		0620-1645	CURVED W-BEAM GUIDE RAIL AT INTERSECTIONS	75	LF	
37		0620-1670	TYPE 31-STRONG POST IN-LINE ANCHOR	6	EA	
38		0677-0002	SELECTED MATERIAL SURFACING	60	TON	
39		0686-0040	CONSTRUCTION SURVEYING TYPE C	1	LS	
40		0689-0003	CPM SCHEDULE	1	LS	
41		0690-0002	SEMI-FORMAL FACILITATION	6000	DOL	1
42		0802-0001	TOPSOIL FURNISHED AND PLACED	250	CY	
43		0804-0001	SEEDING AND SOIL SUPPLEMENTS - FORMULA B INCLUDING MULCH	65	LB	
44		0810-0023	TREE TRIMMING TO A MAX HEIGHT OF 20'	1	LS	
45		0845-0001	UNFORESEEN WATER POLLUTION CONTROL	1000	DOL	1
46		0901-0001	MAINTENANCE AND PROTECTION OF TRAFFIC DURING CONSTRUCTION	1	LS	
47		0901-0320	4" STANDARD PAVEMENT MARKINGS PAINT & BEADS YELLOW	145720	LF	
48		0901-0330	4" STANDARD PAVEMENT MARKINGS PAINT & BEADS WHITE	48660	LF	
49		0931-0003	POST MOUNTED SIGNS TYPE B STEEL SQUARE POST	22	SF	
50		0935-0001	POST MOUNTED SIGNS TYPE F	159	SF	
51		0937-0323	FLEX. DEL. POST GROUND-MNT TYPE GM-1 RED POST W/WHITE SHEETING	30	EA	
52		0937-0330	FLEX. DEL. POST GROUND-MNT TYPE GM-2 WHITE POST W/WHITE/BLANK SHEETING	1	EA	
53		0962-1000	4" WHITE WATERBORNE PAVEMENT MARKINGS	48660	LF	
54		0962-1005	4" YELLOW WATERBORNE PAVEMENT MARKINGS	48640	LF	
55		0971-0001	REMOVE POST MOUNTED SIGNS TYPE B	1	EA	
56		9316-0437	SP WARM MIX ASPHALT FLEXIBLE BASE REPLACEMNT PG64-22 0.3TO<3 MILLION ESALS 25.0 MM MIX 13" DEPTH	500	SY	
57		9620-0001	GUIDE RAIL REPLACEMENT ACROSS STRUCTURE	25	LF	
58		9620-0002	GUIDE RAIL ANCHORBOLT REPLACEMENT	8	EA	

PENNDOT SR 194-027 YORK COUNTY

BID ITEMS

PENNDOT PROJECT NO. 108743

PAGE 1 OF 1