

BID DATE: 10/22/2020
KINSLEY NO. 203100

Line No.	Alt Code	Item No.	Short Description	QTY	Unit	Unit Price
1		0201-0001	CLEARING AND GRUBBING	1	LS	
2		0201-0002	CLEARING AND GRUBBING	1	LS	
3		0203-0001	CLASS 1 EXCAVATION	3951	CY	
4		0203-0004	CLASS 1B EXCAVATION	63	CY	
5		0203-0006	SAW CUTTING	186	LF	
6		0204-0001	CLASS 2 EXCAVATION	143	CY	
7		0204-0150	CLASS 4 EXCAVATION	24	CY	
8		0205-0263	SELECTED BORROW EXCAVATION ROCK CLASS R-3	1348	CY	
9		0205-0264	SELECTED BORROW EXCAVATION ROCK CLASS R-4	254	CY	
10		0205-0266	SELECTED BORROW EXCAVATION ROCK CLASS R-6	595	CY	
11		0205-0268	SELECTED BORROW EXCAVATION ROCK CLASS R-8	627	CY	
12		4205-0300	SELECTED BORROW EXCAVATION (MODIFIED)	46	TON	
13		0212-0001	GEOTEXTILE CLASS 1	636	LF	
14		0212-0014	GEOTEXTILE CLASS 4 TYPE A	3900	SY	
15		0313-0426	SUPERPAVE ASPHALT MIXTURE DESIGN BASE COURSE PG 64S-22 0.3 TO < 3 MILLION ESALS 25.0 MM MIX 6" DEPTH	1074	SY	
16		0313-0431	SUPERPAVE ASPHALT MIXTURE DESIGN BASE COURSE PG 64S-22 0.3 TO < 3 MILLION ESALS 25.0 MM MIX 8 1/2" DEPTH	1166	SY	
17		0350-0106	SUBBASE 6" DEPTH (NO. 2A)	2312	SY	
18		0413-0230	SUPERPAVE ASPHALT MIXTURE DESIGN WEARING COURSE PG 64S-22 0.3 TO < 3 MILLION ESALS 12.5 MM MIX 2" DEPTH SRL-H	22888	SY	
19		0413-1024	SUPERPAVE ASPHALT MIXTURE DESIGN WEARING COURSE (SCRATCH) PG 64S-22 0.3 TO < 3 MILLION ESALS 9.5 MM MIX SRL-L	622	TON	
20		0413-6045	SUPERPAVE ASPHALT MIXTURE DESIGN BINDER COURSE PG 64S-22 0.3 TO < 3 MILLION ESALS 19.0 MM MIX 2 1/2" DEPTH	2215	SY	
21		0413-6047	SUPERPAVE ASPHALT MIXTURE DESIGN BINDER COURSE PG 64S-22 0.3 TO < 3 MILLION ESALS 19.0 MM MIX	8	TON	
22		0460-0001	ASPHALT TACK COAT	45776	SY	
23		0491-0014	MILLING OF ASPHALT PAVEMENT SURFACE 2 1/2" DEPTH MILLED MATERIAL RETAINED BY CONTRACTOR	20673	SY	
24	10	0601-0560	18" THERMOPLASTIC PIPE GROUP VII 12'-2' FILL SHORE/TRENCH BOX 100 YEAR DESIGN LIFE	69	LF	
25	11	0601-0973	18" DUCTILE IRON PIPE SHORE/TRENCH BOX 100 YEAR DESIGN LIFE	69	LF	
26	12	0601-7509	18" REINFORCED CONCRETE PIPE TYPE A 7' - 3' FILL SHORE/TRENCH BOX 100 YEAR DESIGN LIFE	69	LF	
27	20	0601-0564	36" THERMOPLASTIC PIPE GROUP VII 12'-2' FILL SHORE/TRENCH BOX 100 YEAR DESIGN LIFE	157	LF	
28	21	0601-0977	36" DUCTILE IRON PIPE SHORE/TRENCH BOX 100 YEAR DESIGN LIFE	157	LF	
29	22	0601-7538	36" REINFORCED CONCRETE PIPE TYPE A 15' - 3' FILL SHORE/TRENCH BOX 100 YEAR DESIGN LIFE	157	LF	
30	30	0601-7313	18" REINFORCED CONCRETE PIPE TYPE B 15' - 1.5' FILL	85	LF	
31	31	0601-1663	18" SPIRAL RIB ALUMINIZED STEEL PIPE TYPE IR (3/4" X 3/4" X 7 1/2" CORRUGATIONS) 16 GAGE	85	LF	
32		0605-2600	TYPE D ENDWALL	1	EA	
33		0605-2620	TYPE D-W ENDWALL	2	EA	
34		0605-2630	TYPE E-S ENDWALL	1	EA	
35		0605-2730	TYPE M CONCRETE TOP UNIT AND GRATE	2	SET	
36		0605-2850	STANDARD INLET BOX HEIGHT < /= 10'	2	EA	
37		0608-0001	MOBILIZATION	1	LS	
38		0609-0003	INSPECTOR'S FIELD OFFICE AND INSPECTION FACILITIES TYPE B	1	LS	
39		0609-0007	INSPECTOR'S FIELD OFFICE AND INSPECTION FACILITIES TYPE B	1	LS	
40		0609-0009	EQUIPMENT PACKAGE	1	LS	
41		0609-0016	EQUIPMENT PACKAGE	1	LS	
42		0610-7001	4" PAVEMENT BASE DRAIN	636	LF	
43		0610-7400	ADDITIONAL COARSE AGGREGATE FOR EXTRA DEPTH PAVEMENT BASE DRAIN	8	CY	
44		0615-0021	4" SUBSURFACE DRAIN OUTLETS	125	LF	
45		0615-0040	SUBSURFACE DRAIN OUTLET ENDWALL	6	EA	

PENNDOT SR 22-070 LEBANON COUNTY

BID ITEMS

PENNDOT PROJECT NO. 97148

PAGE 1 OF 4

BID DATE: 10/22/2020
KINSLEY NO. 203100

Line No.	Alt Code	Item No.	Short Description	QTY	Unit	Unit Price
46		0615-0066	66" RED SUBSURFACE DRAIN OUTLET MARKER	6	EA	
47		0619-0459	PERMANENT IMPACT ATTENUATING DEVICE TYPE II TEST LEVEL 3 TANGENT (MASH)	6	EA	
48		0619-0744	PERMANENT IMPACT ATTENUATING DEVICE TYPE V TEST LEVEL 3 MASH WIDTHS LESS THAN OR EQUAL TO 36 INCHES	1	EA	
49		0620-0010	TYPICAL AND ALTERNATE CONCRETE BRIDGE BARRIER TRANSITION WITHOUT INLET PLACEMENT	4	EA	
50		0620-0400	TERMINAL SECTION SINGLE	3	EA	
51		0620-0503	REMOVE EXISTING GUIDE RAIL (CONTRACTOR'S PROPERTY)	2424	LF	
52		0620-0900	REMOVE CONCRETE ANCHORAGE	1	EA	
53		0620-1600	TYPE 31-S GUIDE RAIL	1613	LF	
54		0620-1601	TYPE 31-S GUIDE RAIL WITH 7' EXTRA LENGTH POSTS	50	LF	
55		0620-1625	TYPE 31-SC GUIDE RAIL	88	LF	
56		0620-1626	TYPE 31-SC GUIDE RAIL WITH 7' EXTRA LENGTH POSTS	13	LF	
57		0620-1635	TYPE 31-SCC GUIDE RAIL	27	LF	
58		0620-1645	CURVED W-BEAM GUIDE RAIL AT INTERSECTIONS	69	LF	
59		0620-1670	TYPE 31-STRONG POST IN-LINE ANCHOR	3	EA	
60		0623-0001	CONCRETE MEDIAN BARRIER	40	LF	
61		0627-3020	TEMP. BARRIER TEST LEVEL 3 BARRIER DEFLECTION DISTANCE $< \leq 2'$	996	LF	
62		0628-3020	RESET TEMP. BARRIER TEST LEVEL 3 BARRIER DEFLECTION DISTANCE $< \leq 2'$	612	LF	
63		0633-0200	PLAIN CONCRETE MOUNTABLE CURB TYPE A	139	LF	
64		0643-0002	TEMP. CONCRETE MEDIAN BARRIER STRUCTURE MOUNTED	264	LF	
65		0677-0001	SELECTED MATERIAL SURFACING	7	CY	
66		0686-0050	CONSTRUCTION SURVEYING TYPE D	1	LS	
67		0686-0051	CONSTRUCTION SURVEYING TYPE D	1	LS	
68		0689-0003	CPM SCHEDULE	1	LS	
69		0690-0001	INTERNAL FACILITATION	2000	DOL	1
70		0696-0610	TEMP. IMPACT ATTENUATING DEVICE TYPE V (STANDARD) TEST LEVEL 3	4	EA	
71		0697-0610	RESET TEMP. IMPACT ATTENUATING DEVICE TYPE V (STANDARD) TEST LEVEL 3	4	EA	
72		0802-0001	TOPSOIL FURNISHED AND PLACED	331	CY	
73		0804-0001	SEEDING AND SOIL SUPPLEMENTS - FORMULA B INCLUDING MULCH	41	LB	
74		0804-0003	SEEDING AND SOIL SUPPLEMENTS - FORMULA D INCLUDING MULCH	223	LB	
75		0804-0004	SEEDING - FORMULA E INCLUDING MULCH	46	LB	
76		0804-0007	SEEDING AND SOIL SUPPLEMENTS - FORMULA W INCLUDING MULCH	7	LB	
77		0804-0013	SEEDING AND SOIL SUPPLEMENTS - FORMULA D	90	LB	
78		0806-0112	TEMP. SHORT-TERM ROLLED EROSION CONTROL PRODUCT TYPE 2C	1807	SY	
79		0806-0113	TEMP. SHORT-TERM ROLLED EROSION CONTROL PRODUCT TYPE 2D	401	SY	
80		0810-0025	SELECTIVE TREE TRIMMING	10	EA	
81		0810-0052	SELECTIVE TREE REMOVAL	48	EA	
82		0811-0003	TEMP. PROTECTIVE FENCE	462	LF	
83		0845-0001	UNFORESEEN WATER POLLUTION CONTROL	2500	DOL	1
84		0849-0010	ROCK CONSTRUCTION ENTRANCE	1	EA	
85		0851-0003	ROCK APRON	5	SY	
86		0855-0003	PUMPED WATER FILTER BAG	6	EA	
87		0855-0004	REPLACEMENT PUMPED WATER FILTER BAG	6	EA	
88		0860-0000	INLET FILTER BAG FOR TYPE M INLET	1	EA	
89		0867-0012	COMPOST FILTER SOCK 12" DIAMETER	1429	LF	
90		0901-0001	MAINTENANCE AND PROTECTION OF TRAFFIC DURING CONSTRUCTION	1	LS	
91		0901-0002	MAINTENANCE AND PROTECTION OF TRAFFIC DURING CONSTRUCTION	1	LS	
92		0901-0240	ADDITIONAL TRAFFIC CONTROL SIGNS	300	SF	
93		0901-0320	4" STANDARD PAVEMENT MARKINGS PAINT & BEADS YELLOW	8660	LF	
94		0901-0322	8" STANDARD PAVEMENT MARKINGS PAINT & BEADS YELLOW	798	LF	
95		0901-0330	4" STANDARD PAVEMENT MARKINGS PAINT & BEADS WHITE	17066	LF	
96		0901-0332	8" STANDARD PAVEMENT MARKINGS PAINT & BEADS WHITE	834	LF	
97		0901-0461	FULL-MATRIX CHANGEABLE MESSAGE SIGN WITHOUT TELECOMMUNICATIONS	4	EA	
98		0931-0001	POST MOUNTED SIGNS TYPE B	14	SF	
99		0932-0001	POST MOUNTED SIGNS TYPE C	10	SF	

PENNDOT SR 22-070 LEBANON COUNTY
BID ITEMS

PENNDOT PROJECT NO. 97148

BID DATE: 10/22/2020
KINSLEY NO. 203100

Line No.	Alt Code	Item No.	Short Description	QTY	Unit	Unit Price
100		0935-0001	POST MOUNTED SIGNS TYPE F	11	SF	
101		0937-0202	BARRIER MOUNTED DELINEATOR SIDE-MOUNT TYPE O (Y/B)	14	EA	
102		0937-0203	BARRIER MOUNTED DELINEATOR SIDE-MOUNT TYPE O (W/B)	15	EA	
103		0937-0301	FLEXIBLE DELINEATOR POST SURFACE-MOUNT TYPE SM-1 YELLOW POST WITH YELLOW SHEETING	24	EA	
104		0937-0337	FLEXIBLE DELINEATOR POST GROUND-MOUNT TYPE GM-2 RED POST WITH RED/WHITE SHEETING	1	EA	
105		0941-0001	RESET POST MOUNTED SIGNS TYPE B	3	EA	
106		0942-0002	RESET POST MOUNTED SIGNS TYPE C	1	EA	
107		0945-0001	RESET POST MOUNTED SIGNS TYPE F	3	EA	
108		0962-1000	4" WHITE WATERBORNE PAVEMENT MARKINGS	12431	LF	
109		0962-1005	4" YELLOW WATERBORNE PAVEMENT MARKINGS	5832	LF	
110		0963-0001	PAVEMENT MARKING REMOVAL	1895	SF	
111		0963-0004	4" PAVEMENT MARKING REMOVAL	2239	LF	
112		0963-0008	8" PAVEMENT MARKING REMOVAL	54	LF	
113		0965-0021	24" WHITE PREFORMED THERMOPLASTIC PAVEMENT MARKINGS	495	LF	
114		0966-0017	SNOWPLOWABLE RAISED PAVEMENT MARKER TWO WAY HOLDER WITH REFLECTOR (Y/B)	125	EA	
115		0966-0018	SNOWPLOWABLE RAISED PAVEMENT MARKER TWO WAY HOLDER WITH REFLECTOR (W/B)	138	EA	
116		0966-0103	SNOWPLOWABLE RAISED PAVEMENT MARKER TWO WAY BRIDGE DECK HOLDER WITH REFLECTOR (Y/B)	2	EA	
117		0966-0104	SNOWPLOWABLE RAISED PAVEMENT MARKER TWO WAY BRIDGE DECK HOLDER WITH REFLECTOR (W/B)	2	EA	
118		0971-0001	REMOVE POST MOUNTED SIGNS TYPE B	1	EA	
119		1001-1140	CLASS C CEMENT CONCRETE	11	CY	
120		1018-0001	REMOVAL OF EXISTING BRIDGE	1	LS	
121		1018-0060	REMOVAL OF EXISTING CULVERT	1	LS	
122		1999-0000	TRAINEES FOR PROJECTS 100% STATE FUNDED	1000	HR	
123	40	8010-0010	BRIDGE STRUCTURE AS DESIGNED S-38740	1	LS	
		0204-0100	CLASS 3 EXCAVATION	1542	CY	
		0212-0014	GEOTEXTILE, CLASS 4, TYPE A	1352	SY	
		0680-0121	MEMBRANE WATERPROOFING SYSTEM INSTALLED ON OTHER SURFACES	48	SY	
		0703-0025	NO. 57 COARSE AGGREGATE	158	CY	
		1001-1000	CLASS AAAP CEMENT CONCRETE	444	CY	
		1001-1080	CLASS AA CEMENT CONCRETE	73	CY	
		1001-1120	CLASS A CEMENT CONCRETE	127	CY	
		0205-0292	STRUCTURE BACKFILL	348	CY	
		1019-0040	PROTECTIVE COATING FOR REINFORCED CONCRETE SURFACES (PENETRATING SEALERS, REINFORCED CONCRETE SUBSTRUCTURE SURFACES)	41	SY	
		1019-0050	PROTECTIVE COATING FOR REINFORCED CONCRETE SURFACES (PENETRATING SEALERS, BRIDGE SUPERSTRUCTURE)	1175	SY	
		1080-0439	PRESTRESSED CONCRETE SPREAD BOX BEAMS, 48" X 33"	510	LF	
			METAL CURB DRAINS	4	EA	
124	40	1001-0980	MECHANICAL TEXTURING WITH LONGITUDINAL SAWED GROOVES	971	SY	
125	40	1002-0052	REINFORCEMENT BARS EPOXY COATED	129116	LB	
126	40	1002-0155	MECHANICAL SPLICE SYSTEM FOR NO. 8 REBAR EPOXY COATED	52	EA	
127	40	1002-0157	MECHANICAL SPLICE SYSTEM FOR NO. 10 REBAR EPOXY COATED	32	EA	
128	40	1005-1725	STEEL HP12X74 TEST PILE	4	EA	
129	40	1005-1825	STEEL HP12X74 PRODUCTION PILE	1182	LF	
130	40	1005-2025	STEEL HP12X74 PILE TIP REINFORCEMENT (HEAVY DUTY)	38	EA	
131	40	9005-0500	MANDATORY PRE-DRILLING FOR DRIVEN PILES	745	LF	
132	41	8000-0010	PRESTRESSED CONCRETE BRIDGE STRUCTURE	1	LS	
133	42	8100-0010	STEEL BRIDGE STRUCTURE	1	LS	
134	50	8510-0001	PRECAST CONCRETE BOX CULVERT AS DESIGNED S-39038	1	LS	
			8'-0" X 7'-6" PRECAST REINFORCED CONCRETE BOX CULVERT SEGMENTS	66.5	LF	
			PRECAST REINFORCED CONCRETE BOX CULVERT END SECTIONS	6	EA	

PENNDOT SR 22-070 LEBANON COUNTY
BID ITEMS

BID DATE: 10/22/2020
KINSLEY NO. 203100

Line No.	Alt Code	Item No.	Short Description	QTY	Unit	Unit Price
			CLASS 3 EXCAVATION	657	CY	
			SELECTED BORROW EXCAVATION ROCK, CLASS R-8, CHOKED WITH R-4 AND NATIVE STREAMBED MATERIAL	84	CY	
			SELECTED BORROW EXCAVATION, STRUCTURE BACKFILL	171	CY	
			CLASS AA CEMENT CONCRETE	5	CY	
			CLASS A CEMENT CONCRETE	37	CY	
			NO. 2A COARSE AGGREGATE	127	CY	
			NO. 8 COARSE AGGREGATE	69	CY	
			NO. 57 COARSE AGGREGATE	9	CY	
			MEMBRANE WATERPROOFING INSTALLED ON OTHER SURFACES	69	SY	
			PROTECTIVE COATING FOR REINFORCED CONCRETE SURFACES, (PENETRATING SEALER, REINFORCED CONCRETE SUBSTRUCTURE SURFACES)	21	SY	
135	50	1002-0053	REINFORCEMENT BARS EPOXY COATED	4256	LB	
136	51	8520-0001	CAST-IN-PLACE REINFORCED CONCRETE BOX CULVERT	1	LS	
137		9000-0001	TEMP. CONCRETE BARRIER COFFERDAM	1	LS	
138		9000-0002	TEMP. ARCH SUPPORT	1	LS	
139		9000-0003	TEMP. PUMP BYPASS	1	LS	
140		9000-0004	COVID-19 SAFETY PLAN SIGN	4	EA	
141		9000-0120	SOLUTION CAVITY EXCAVATION	33	CY	
142		9000-0500	PERMANENT RIGHT-OF-WAY MONUMENTS	2	EA	
143		9203-0101	TEMP. EXCAVATION SUPPORT AND PROTECTION SYSTEM	1	LS	
144		9203-0102	TEMP. EXCAVATION SUPPORT AND PROTECTION SYSTEM	1	LS	
145		9204-0100	OVEREXCAVATION AND BACKFILL WITH CLASS C CEMENT CONCRETE	28	CY	
146		9901-0400	TRAFFIC SIGNAL TECHNICIAN (AS DIRECTED)	1000	DOL	1