

SUBCONTRACT AND MATERIAL SUPPLY OPPORTUNITIES

Project: 97148		Advertised	
Short Description:	Allentown Blvd over Beach-B	Org Code:	0800
County:	Lebanon	SR: 22	Section: 070
District:	08	Group ID: ---	Municipality: BETHEL

PROJECT DESCRIPTION:

This project involves the replacement of the existing bridge carrying SR 0022 Sec. 070 over Beach Run in Bethel Township, Lebanon County. The bridge will be replaced with a single span prestressed concrete spread box beam bridge with reinforced concrete integral abutments. Approach roadway reconstruction, drainage replacement, guide rail replacement, pavement markings and signing will also be included as part of the project. The project will utilize half width construction to maintain two lanes of traffic, one in each direction. This project also includes the replacement of an existing single span concrete arch culvert with a single span precast concrete box culvert. This culvert is located in North Annville Township on Route 934. Work also includes minor roadway approach work, shoulder widening, a pipe replacement under Hill Church Road, guide rail replacement along Ono Road, and other miscellaneous construction, all as indicated on the approved drawings included in the Bid Package for STATE ROUTE 0934, SECTION 010, in LEBANON COUNTY, NORTH ANNVILLE TOWNSHIP, from Segment 0120 Offset 3257 to Segment 0130 Offset 0454, for an overall project length of 787.00 linear feet (0.149 mile).

BID DATE: 10/22/2020

CONTACT: KINSLEY CONSTRUCTION, INC.
BARRY FAUTH
bfauth@kinsleyconstruction.com
Phone: (717) 815-6997
Cell: (717) 324-1930
Fax: (717) 845-3111

SUBCONTRACT AND MATERIAL SUPPLY OPPORTUNITIES

1. CLEARING & GRUBBING, TREE TRIMMING AND SELECTIVE TREE REMOVAL
2. MAINTENANCE AND PROTECTION OF TRAFFIC SIGNING
3. FLAGGING SERVICES
4. DRAINAGE INLETS AND PIPE
5. PAVEMENT BASE DRAINS
6. CONCRETE CURB AND CONCRETE SIDEWALK
7. PAVEMENT MARKINGS
8. SNOWPLOWABLE RAISED PAVEMENT MARKERS
9. TRUCKING
10. MILLING ASPHALT PAVEMENT
11. SURVEYING SERVICES
12. SEEDING, MULCHING, MATTING AND TEMP. PROTECTIVE FENCE
13. COMPOST FILTER SOCK
14. IN PLACE ASPHALT PAVING
15. GUIDE RAIL
16. TEMPORARY BARRIER AND TEMPORARY ATTENUATORS
17. CONCRETE MEDIAN BARRIER
18. POST MOUNTED SIGNS
19. REBAR (FURNISH AND/OR PLACE)
20. PRESTRESSED CONCRETE SPREAD BOX BEAMS, 48" X 33"

SUBCONTRACT AND MATERIAL SUPPLY OPPORTUNITIES

Project: 97148

Advertised

Short Description:	Allentown Blvd over Beach-B	Org Code:	0800
County:	Lebanon	SR: 22	Section: 070
District:	08	Group ID: ---	Municipality: BETHEL

21. DECK PANS
22. METAL CURB DRAINS
23. STEEL HP12X74 PILES
24. MANDATORY PRE-DRILLING FOR DRIVEN PILES
25. TEMPORARY PUMP BYPASS
26. PRECAST CONCRETE BOX CULVERT (8'-0" x 7'-6" x 66.5')
27. MECHANICAL TEXTURING WITH LONGITUDINAL SAWED GROOVES
28. PROTECTIVE COATING FOR REINFORCED CONCRETE SURFACES
29. SUPPLY OF GEOTEXTILE MATERIALS AND MEMBRANE WATERPROOFING
30. FURNISH AGGREGATES, CONCRETE AND SUPERPAVE ASPHALT MATERIALS