

BID DATE: 12/23/2020
KINSLEY NO. 203116

Line No.	Alt Code	Item No.	Short Description	QTY	Unit	Unit Price
100		2108-0001	CONSTRUCTION SCHEDULE	1	LS	
200		2201-0001	CLEARING AND GRUBBING	1	LS	
300		2203-0001	CLASS 1 EXCAVATION	5537	CY	
400		2203-0004	CLASS 1B EXCAVATION	1689	CY	
500		2203-2101	TEMPORARY SHORING	1	LS	
600		2204-0001	CLASS 2 EXCAVATION	29	CY	
700		2204-0100	CLASS 3 EXCAVATION	5771	CY	
800		2204-1008	OVER-EXCAVATION AND BACKFILLING UNDER FOUNDATIONS CLASS C CONC.	308	CY	
900		0205-0100	FOREIGN BORROW EXCAVATION	2142	CY	
1000		0313-0437	SUPERPAVE ASPHALT MIXTURE DESIGN BASE PG64S-22 0.3TO<3 MILLION ESALS 25.0 MM MIX	910	TON	
1100		0313-0637	SUPERPAVE ASPHALT MIXTURE DESIGN BASE PG64S-22 10TO<30 MILLION ESALS 25.0 MM MIX	1322	TON	
1200		2350-0121	SUBBASE (NO. 2A)	2326	TON	
1300		0413-0240	SUPERPAVE ASPHALT MIXTURE DESIGN WEARING PG64S-22 0.3TO<3 MILLION ESALS 12.5 MM MIX SRL-H	339	TON	
1400		0413-0255	SUPERPAVE ASPHALT MIXTURE DESIGN WEARING PG64S-22 0.3TO<3 MILLION ESALS 9.5 MM MIX SRL-H	302	TON	
1500		2413-0437	SUPERPAVE ASPHALT MIXTURE DESIGN WEARING PG64E-22 10TO<30 MILLION ESALS 9.5 MM MIX SRL-E	1137	TON	
1600		0413-1024	SUPERPAVE ASPHALT MIXTURE DESIGN WEARING SCRATCH) PG64S-22 0.3TO<3 MILLION ESALS 9.5 MM MIX SRL-L	73	TON	
1700		0413-2074	SUPERPAVE ASPHALT MIXTURE DESIGN WEARING (LEVELING) PG64S-22 0.3TO<3 MILLION ESALS 9.5 MM MIX SRL-L	188	TON	
1800		0413-6047	SUPERPAVE ASPHALT MIXTURE DESIGN BINDER PG64S-22 0.3TO<3 MILLION ESALS 19.0 MM MIX	146	TON	
1900		2413-6067	SUPERPAVE ASPHALT MIXTURE DESIGN BINDER PG64S-22 10 TO < 30 MILLION ESALS 19 MM MIX	595	TON	
2000		0460-0001	ASPHALT TACK COAT	2539	SY	
2100		2491-0063	MILLING OF ASPHALT PAVEMENT SURFACE 1 1/2" DEPTH	9106	SY	
2200		2491-0070	MILLING OF ASPHALT PAVEMENT SURFACE VARIABLE DEPTH	2426	SY	
2300		2499-1000	PAYMENT ADJUSTMENT FOR ASPHALT MATERIALS	1	PDA	5000
2400		2601-0311	12" THERMOPLASTIC PIPE GROUP I 15'-1.5' FILL	10	LF	
2500		0608-0001	MOBILIZATION	1	LS	
2600		2609-0003	INSPECTOR'S FIELD OFFICE AND INSPECTION FACILITIES TYPE B	1	LS	
2700		0610-7002	6" PAVEMENT BASE DRAIN	933	LF	
2800		2610-7002	6" PAVEMENT BASE DRAIN	2692	LF	
2900		0615-0022	6" SUBSURFACE DRAIN OUTLETS	45	LF	
3000		0615-0040	SUBSURFACE DRAIN OUTLET ENDWALL	3	EA	
3100		0615-0066	66" RED SUBSURFACE DRAIN OUTLET MARKER	3	EA	
3200		2616-0600	ALUMINUM ALLOY END SECTIONS 16 GAGE FOR 12" PIPE	2	EA	
3300		2620-0010	TYPICAL AND ALTERNATE CONCRETE BRIDGE BARRIER TRANSITION WITHOUT INLET PLACEMENT	4	EA	
3400		0620-0012	THRIE-BEAM TO PA TYPE 10M BRIDGE BARRIER TRANSITION WITHOUT INLET PLACEMENT	4	EA	
3500		2620-0400	TERMINAL SECTION SINGLE	2	EA	
3600		2620-0503	REMOVE EXISTING GUIDE RAIL	1560	LF	
3700		2620-1250	VEHICLE ATTENUATING TERMINAL END TREATMENT (V.A.T.E.T.) TYPE II TEST LEVEL 3 - MASH (ENERGY ABSORBING TERMINALS TANGENT)	1	EA	
3800		3620-1250	TEMPORARY VEHICLE ATTENUATING TERMINAL END TREATMENT (V.A.T.E.T.) TYPE II TEST LEVEL 3 - MASH (ENERGY ABSORBING TERMINALS TANGENT) INCLUDING MAINTENANCE AND REMOVAL	5	EA	
3900		2620-1600	TYPE 31-S GUIDE RAIL	1355	LF	
4000		2620-1601	TYPE 31-S GUIDE RAIL WITH 7' EXTRA LENGTH POSTS	175	LF	
4100		2620-1625	TYPE 31-SC GUIDE RAIL	50	LF	
4200		2620-1645	CURVED W-BEAM GUIDE RAIL AT INTERSECTIONS	52.5	LF	
4300		2620-1650	TYPE 31-STRONG POST END TREATMENT	1	EA	

**BID DATE: 12/23/2020
KINSLEY NO. 203116**

Line No.	Alt Code	Item No.	Short Description	QTY	Unit	Unit Price
4400		2620-1670	TYPE 31-STRONG POST IN-LINE ANCHOR	2	EA	
4500		2622-0010	REMOVE CONCRETE GLARE SCREEN	354	LF	
4600		2622-0025	REMOVE AND STORE CONCRETE GLARE SCREEN	1442	LF	
4700		2622-0035	RESET AND INSTALL CONCRETE GLARE SCREEN	1442	LF	
4800		2622-2001	PRECAST PIER TRANSITION	2	EA	
4900		4624-0001	RIGHT-OF-WAY FENCE TYPE 1 8 FOOT HEIGHT	283	LF	
5000		2624-0100	RIGHT-OF-WAY FENCE TYPE 2	503	LF	
5100		2624-0301	END POSTS FOR TYPE 2 RIGHT-OF-WAY FENCE	1	EA	
5200		2624-0401	CORNER POSTS FOR TYPE 2 RIGHT-OF-WAY FENCE	1	EA	
5300		2627-1003	FURNISH AND INSTALL TEMPORARY CONCRETE GLARE SCREEN	1966	LF	
5400		2627-2003	REMOVE TEMPORARY CONCRETE GLARE SCREEN	1966	LF	
5500		2627-2500	TEMPORARY CONCRETE BARRIER AND TEMPORARY IMPACT ATTENUATOR	1720	LF	
5600		0630-0001	PLAIN CEMENT CONCRETE CURB	645	LF	
5700		3630-0001	PLAIN CEMENT CONCRETE CURB 4" HEIGHT	335	LF	
5800		0630-0010	PLAIN CEMENT CONCRETE CURB INCLUDING REMOVAL OF EXISTING CURB	7	LF	
5900		2660-0031	SONIC NAP ALERT PATTERN (S.N.A.P.)	3152	EA	
6000		0676-0001	CEMENT CONCRETE SIDEWALK	285	SY	
6100		0680-0003	MEMBRANE WATERPROOFING	181	SY	
6200		2686-0010	CONSTRUCTION SURVEYING TYPE A	1	LS	
6300		2686-0050	CONSTRUCTION SURVEYING TYPE D	1	LS	
6400	OA1	0695-0002	DETECTABLE WARNING SURFACE CAST IRON	44	SF	
6500	OA2	0695-0003	DETECTABLE WARNING SURFACE POLYMER CONCRETE	44	SF	
6600	OA3	0695-0004	DETECTABLE WARNING SURFACE POLYMER COMPOSITE	44	SF	
6700		2696-0200	REPAIR OF TEMPORARY IMPACT ATTENUATING DEVICE	1	PDA	10000
6800		0703-0025	NO. 57 COARSE AGGREGATE	20	CY	
6900		3803-0002	PLACING STOCKPILED TOPSOIL MIXTURE	1688	CY	
7000		2804-0013	SEEDING AND SOIL SUPPLEMENTS - FORMULA D	40	LB	
7100		2804-0014	SEEDING - FORMULA E	30	LB	
7200		2804-0102	SEEDING AND SOIL SUPPLEMENTS - FORMULA BT-1	462	LB	
7300		0806-0113	TEMPORARY SHORT-TERM ROLLED EROSION CONTROL PRODUCT TYPE 2D	11014	SY	
7400		2808-3072	RED MAPLE - (1 1/2" CAL. B&B)	10	EA	
7500		2808-4093	SILKY DOGWOOD (18-24" HT. 3 GAL CONTAINER)	25	EA	
7600		2808-6053	WINTERBERRY (18-24" HT. 3 GAL. CONTAINER)	30	EA	
7700		2810-0001	SELECTIVE TREE REMOVAL AND TRIMMING	0.3	AC	
7800		2845-0001	EROSION AND SEDIMENTATION CONTROL DURING CONSTRUCTION	1	PDA	5000
7900		0855-0003	PUMPED WATER FILTER BAG	2	EA	
8000		0855-0004	REPLACEMENT PUMPED WATER FILTER BAG	2	EA	
8100		0860-0000	INLET FILTER BAG FOR TYPE M INLET	6	EA	
8200		0867-0018	COMPOST FILTER SOCK 18" DIAMETER	2458	LF	
8300		2901-0001	MAINTENANCE AND PROTECTION OF TRAFFIC	1	LS	
8400		2901-0203	ARROW PANEL	2	EA	
8500		2901-0301	4" WHITE HIGHLY REFLECTORIZED TEMPORARY POLYUREA PAVEMENT MARKINGS	5504	LF	
8600		2901-0302	4" YELLOW HIGHLY REFLECTORIZED TEMPORARY POLYUREA PAVEMENT MARKINGS	1426	LF	
8700		2901-0320	4" STANDARD PAVEMENT MARKINGS PAINT & BEADS YELLOW	8453	LF	
8800		2901-0321	6" STANDARD PAVEMENT MARKINGS PAINT & BEADS YELLOW	1879	LF	
8900		2901-0330	4" STANDARD PAVEMENT MARKINGS PAINT & BEADS WHITE	13652	LF	
9000		2901-0331	6" STANDARD PAVEMENT MARKINGS PAINT & BEADS WHITE	3592	LF	
9100		2901-0334	24" STANDARD PAVEMENT MARKINGS PAINT & BEADS WHITE	124	LF	
9200		2901-0498	PORTABLE CHANGEABLE MESSAGE SIGNS 3 LINES 8 CHARACTERS PER LINE	4	EA	
9300		2901-0499	PORTABLE CHANGEABLE MESSAGE SIGNS 3 LINES 12 CHARACTERS PER LINE	2	EA	
9400		2901-0501	SHADOW VEHICLE WITH TRUCK MOUNTED ATTENUATOR (TMA)	2	EA	
9500		4901-9999	COVID-19 SAFETY PLAN SIGNS	3	EA	
9600		2931-0001	POST MOUNTED SIGNS TYPE B	64	SF	
9700		2931-1001	RELOCATION OF POST MOUNTED SIGNS TYPE B	5	EA	
9800		2935-0001	POST MOUNTED SIGNS TYPE F	15.25	SF	

**BID DATE: 12/23/2020
KINSLEY NO. 203116**

Line No.	Alt Code	Item No.	Short Description	QTY	Unit	Unit Price
9900		2936-0200	STRUCTURE MOUNTED FLAT SHEET ALUMINUM SIGNS	36	SF	
10000		2939-0001	POST MOUNTED SIGNS TYPE M - MEDIAN BARRIER SUPPORT	6	SF	
10100		2962-1000	4" WHITE WATERBORNE PAVEMENT MARKINGS	1344	LF	
10200		2962-1003	12" WHITE WATERBORNE PAVEMENT MARKINGS	67	LF	
10300		2962-1004	24" WHITE WATERBORNE PAVEMENT MARKINGS	51	LF	
10400		2962-1005	4" YELLOW WATERBORNE PAVEMENT MARKINGS	2852	LF	
10500		2963-0002	PAVEMENT MARKING REMOVAL	17068	LF	
10600		2964-0025	6" WHITE HIGHLY REFLECTORIZED POLYUREA PAVEMENT MARKINGS	4334	LF	
10700		2964-0026	6" YELLOW HIGHLY REFLECTORIZED POLYUREA PAVEMENT MARKINGS	3152	LF	
10800		0971-0001	REMOVE POST MOUNTED SIGNS TYPE B	4	EA	
10900		2001-0001	CLASS AA CEMENT CONCRETE	64	CY	
11000		2001-0010	CLASS A CEMENT CONCRETE	751	CY	
11100		2001-0611	6" STRUCTURE FOUNDATION DRAIN	80	LF	
11200		1001-0730	SELECTED BORROW EXCAVATION STRUCTURE BACKFILL	3448	CY	
11300		2001-0900	ARCHITECTURAL SURFACE TREATMENT	4747	SF	
11400		2001-0960	CLASS AAAP CEMENT CONCRETE	182	CY	
11500		2001-0970	MECHANICAL TEXTURING WITH TRANSVERSE SAWED GROOVES	440	SY	
11600		1002-0053	REINFORCEMENT BARS EPOXY COATED	122373	LB	
11700		2016-0001	PROTECTIVE FENCE	264	LF	
11800		2018-0001	REMOVAL OF BRIDGE NO. EB-311 MP 250.09	1	LS	
11900		1019-0010	PROTECTIVE COATING FOR REINFORCED CONCRETE SURFACES (BOILED LINSEED OIL)	484	SY	
12000		2044-0800	AESTHETIC CONCRETE COATING	1	LS	
12100		1050-0020	FABRICATED STRUCTURAL STEEL	146000	LB	
12200		1050-0085	LAMINATED NEOPRENE BEARING PAD	17	EA	
12300		1056-0470	SHEAR CONNECTORS	2195	EA	
12400		2090-0200	UNDERDECK PROTECTION SHIELDS	7358	SF	
12500		2090-0300	CANTILEVERED COMBINATION WORK PLATFORMS AND PROTECTION SHIELDS	264	LF	
12600		1091-0331	EPOXY INJECTION CRACK SEAL	100	LF	
12700		4000-0001	DESIGN OF TEMPORARY BRIDGE	1	LS	
12800		4000-0002	CONSTRUCT TEMPORARY BRIDGE	1	LS	
12900		4000-0003	RUMBLE PAD CONSTRUCTION ENTRANCE	3	EA	
13000		4000-0004	AIR BRIDGE	1	LS	
13100		4000-0005	TEMPORARAY SIDEWALK PROTECTIVE FENCE	526	LF	
13200		4000-0006	TEMPORARY RELOCATION OF SCHOOL ZONE FLASHING WARNING SIGN	2	EA	
13300		4000-0007	WINTER SIDEWALK MAINTENANCE	1	PDA	20000