

**BID DATE: 01/28/2021
KINSLEY NO. 213006**

Line No.	Alt Code	Item No.	Short Description	QTY	Unit	Unit Price
1		0201-0001	CLEARING AND GRUBBING	1	LS	
2		0203-0001	CLASS 1 EXCAVATION	1832	CY	
3		0203-0006	SAW CUTTING	51	LF	
4		0205-0263	SELECTED BORROW EXCAVATION ROCK CLASS R-3	414	CY	
5		0205-0264	SELECTED BORROW EXCAVATION ROCK CLASS R-4	204	CY	
6		0212-0001	GEOTEXTILE CLASS 1	750	LF	
7		0212-0014	GEOTEXTILE CLASS 4 TYPE A	2465	SY	
8		0223-0001	GEOSYNTHETIC REINFORCED SOIL SLOPE TYPE A	203	SF	
9		0313-0326	SP BASE PG64S-22 <0.3 MILLION ESALs 25.0 MM 6" DEPTH	1790	SY	
10		0350-0106	SUBBASE 6" DEPTH (NO. 2A)	2060	SY	
11		0413-0195	SP WEARING PG64S-22 <0.3 MILLION ESALS 9.5 MM 1 1/2" DEPTH SRL-L	2588	SY	
12		0413-2059	SP WEARING (LEVELING) PG64S-22 <0.3 MILLION ESALS 9.5 MM SRL-L	4	TON	
13		0460-0003	ASPHALT TACK COAT (NTT/CNTT)	2621	SY	
14		0461-0001	ASPHALT PRIME COAT	529	SY	
15		0491-0012	MILLING OF ASPHALT PAVEMENT SURFACE 1 1/2" DEPTH MILLED MATERIAL RETAINED BY CONTRACTOR	798	SY	
16		0601-0313	18" THERMOPLASTIC PIPE GROUP I 15'-1.5' FILL	76	LF	
17		0601-0315	24" THERMOPLASTIC PIPE GROUP I 15'-1.5' FILL	40	LF	
18		0601-5431	CLASS C CEMENT CONCRETE FOR MISCELLANEOUS DRAINAGE	506	CY	
19		0605-2730	TYPE M CONCRETE TOP UNIT AND GRATE	3	SET	
20		0605-2850	STANDARD INLET BOX HEIGHT < /= 10'	3	EA	
21		0608-0001	MOBILIZATION	1	LS	
22		0609-0003	INSPECTOR'S FIELD OFFICE AND INSPECTION FACILITIES TYPE B	1	LS	
23		0609-0009	EQUIPMENT PACKAGE	1	LS	
24		0610-7002	6" PAVEMENT BASE DRAIN	563	LF	
25		0615-0022	6" SUBSURFACE DRAIN OUTLETS	89	LF	
26		0615-0040	SUBSURFACE DRAIN OUTLET ENDWALL	3	EA	
27		0615-0066	66" RED SUBSURFACE DRAIN OUTLET MARKER	3	EA	
28		0619-0458	PERM. IMPACT ATTENUATING DEVICE TYPE II TEST LEVEL 2 TANGENT (MASH)	2	EA	
29		4620-0503	REMOVE EXISTING GUIDE RAIL (CONTRACTOR'S PROPERTY)	863	LF	
30		0620-1600	TYPE 31-S GUIDE RAIL	813	LF	
31		0620-1601	TYPE 31-S GUIDE RAIL WITH 7' EXTRA LENGTH POSTS	63	LF	
32		0620-1625	TYPE 31-SC GUIDE RAIL	25	LF	
33		0686-0020	CONSTRUCTION SURVEYING TYPE B	1	LS	
34		0689-0005	CPM SCHEDULE WITH UPDATES	1	LS	
35		0690-0001	INTERNAL FACILITATION	1000	DOL	1
36		0703-0020	NO. 1 COARSE AGGREGATE	33	CY	
37		0703-0025	NO. 57 COARSE AGGREGATE	29	CY	
38		0804-0013	SEEDING AND SOIL SUPPLEMENTS - FORMULA D	30	LB	
39		0804-0014	SEEDING - FORMULA E	5	LB	
40		0805-0022	MULCHING - STRAW	1	TON	
41		0806-0121	TEMPORARY EXTENDED-TERM ROLLED EROSION CONTROL PRODUCT TYPE 3B	229	SY	
42		0810-0027	TREE TRIMMING TO AN UNLIMITED HEIGHT	751	LF	
43		0845-0001	UNFORESEEN WATER POLLUTION CONTROL	1000	DOL	1
44		4850-0033	ROCK CLASS R-5 ((INCLUDES EXCAVATION))	11	CY	
45		0855-0003	PUMPED WATER FILTER BAG	1	EA	
46		0855-0004	REPLACEMENT PUMPED WATER FILTER BAG	1	EA	
47		0901-0001	MAINTENANCE AND PROTECTION OF TRAFFIC DURING CONSTRUCTION	1	LS	
48		0901-0240	ADDITIONAL TRAFFIC CONTROL SIGNS	100	SF	
49		0901-0320	4" STANDARD PAVEMENT MARKINGS PAINT & BEADS YELLOW	1920	LF	
50		0901-0330	4" STANDARD PAVEMENT MARKINGS PAINT & BEADS WHITE	1968	LF	
51		0931-0001	POST MOUNTED SIGNS TYPE B	18	SF	
52		0937-0339	FLEXIBLE DELINEATOR POST GROUND-MOUNT TYPE GM-2 RED POST WITH WHITE/BLANK SHEETING	2	EA	
53		0962-1000	4" WHITE WATERBORNE PAVEMENT MARKINGS	1968	LF	
54		0962-1005	4" YELLOW WATERBORNE PAVEMENT MARKINGS	1920	LF	
55		9000-0001	TEMPORARY PUMP BYPASS SYSTEM	1	EA	

BID DATE: 01/28/2021
KINSLEY NO. 213006

Line No.	Alt Code	Item No.	Short Description	QTY	Unit	Unit Price
56		9000-0002	REMOVE TEMPORARY BARRIER (CONTRACTOR'S PROPERTY)	584	LF	
57		9000-0003	REMOVE TEMPORARY SIGNALS AND ELECTRICAL SERVICE	1	LS	
58		9000-0004	WEEP HOLE	16	EA	
59		9000-0005	SECTION 850 ROCK ENCASED IN CLASS C CONCRETE	1874	CY	
60		9000-0310	ANTI-WASHOUT ADMIXTURE	50	CY	
61		9000-0500	COVID-19 SAFETY PLAN SIGN	2	EA	
62		9100-0001	TOE WALL	336	LF	