

**BID DATE: 02/11/2021  
KINSLEY NO. 213010**

Line No.	Alt Code	Item No.	Short Description	QTY	Unit	Unit Price
1		0201-0001	CLEARING AND GRUBBING	1	LS	
2		0203-0001	CLASS 1 EXCAVATION	1398	CY	
3		0203-0006	SAW CUTTING	136	LF	
4		0204-0001	CLASS 2 EXCAVATION	12	CY	
5		0204-0150	CLASS 4 EXCAVATION	20	CY	
6		0205-0263	SELECTED BORROW EXCAVATION ROCK CLASS R-3	29	CY	
7		0205-0264	SELECTED BORROW EXCAVATION ROCK CLASS R-4	189	CY	
8		0212-0014	GEOTEXTILE CLASS 4 TYPE A	1248	SY	
9		0313-0424	SUPERPAVE ASPHALT MIXTURE DESIGN BASE PG64S-22 0.3TO<3 MILLION ESALs 25.0 MM MIX 5" DEPTH	849	SY	
10		0350-0104	SUBBASE 4" DEPTH (NO. 2A)	51	SY	
11		0350-0106	SUBBASE 6" DEPTH (NO. 2A)	1225	SY	
12		0350-0121	SUBBASE (NO. 2A)	97	TON	
13		0413-0246	SUPERPAVE ASPHALT MIXTURE DESIGN WEARING PG64S-22 0.3TO<3 MILLION ESALs 9.5 MM MIX 1 1/2" DEPTH SRL-G	1089	SY	
14		0413-1024	SUPERPAVE ASPHALT MIXTURE DESIGN WEARING (SCRATCH) PG64S-22 0.3TO<3 MILLION ESALs 9.5 MM MIX SRL-L	6	TON	
15		0413-6045	SUPERPAVE ASPHALT MIXTURE DESIGN BINDER PG64S-22 0.3TO<3 MILLION ESALs 19.0 MM MIX 2 1/2" DEPTH	900	SY	
16		0460-0001	ASPHALT TACK COAT	2127	SY	
17		0461-0001	ASPHALT PRIME COAT	376	SY	
18		0491-0013	MILLING OF ASPHALT PAVEMENT SURFACE 2" DEPTH MILLED MATERIAL RETAINED BY CONTRACTOR	189	SY	
19		0601-0311	12" THERMOPLASTIC PIPE GROUP I 15'-1.5' FILL	40	LF	
20		0608-0001	MOBILIZATION	1	LS	
21		0609-0008	INSPECTOR'S FIELD OFFICE AND INSPECTION FACILITIES TYPE C	1	LS	
22		0609-0009	EQUIPMENT PACKAGE	1	LS	
23		0619-0459	PERMANENT IMPACT ATTENUATING DEVICE TYPE II TEST LEVEL 3 TANGENT (MASH)	3	EA	
24		0620-0400	TERMINAL SECTION SINGLE	1	EA	
25		0620-0503	REMOVE EXISTING GUIDE RAIL (CONTRACTOR'S PROPERTY)	357	LF	
26		0620-1600	TYPE 31-S GUIDE RAIL	313	LF	
27		0620-1645	CURVED W-BEAM GUIDE RAIL AT INTERSECTIONS	13	LF	
28		0620-1670	TYPE 31-STRONG POST IN-LINE ANCHOR	1	EA	
29		0686-0060	CONSTRUCTION SURVEYING TYPE D MODIFIED	1	LS	
30		0689-0003	CPM SCHEDULE	1	LS	
31		0690-0001	INTERNAL FACILITATION	1000	DOL	1
32		0802-0001	TOPSOIL FURNISHED AND PLACED	39	CY	
33		0803-0001	PLACING STOCKPILED TOPSOIL	69	CY	
34		0804-0001	SEEDING AND SOIL SUPPLEMENTS - FORMULA B INCLUDING MULCH	9	LB	
35		0804-0004	SEEDING - FORMULA E INCLUDING MULCH	14	LB	
36		0804-0005	SEEDING AND SOIL SUPPLEMENTS - FORMULA N INCLUDING MULCH	29	LB	
37		0806-0112	TEMPORARY SHORT-TERM ROLLED EROSION CONTROL PRODUCT TYPE 2C	559	SY	
38		0810-0052	SELECTIVE TREE REMOVAL	1	EA	
39		0811-0003	TEMPORARY PROTECTIVE FENCE	268	LF	
40		0845-0001	UNFORESEEN WATER POLLUTION CONTROL	2500	DOL	1
41		0850-0031	ROCK CLASS R-3	3	CY	
42		0850-0034	ROCK CLASS R-6	7	CY	
43		4850-0036	ROCK CLASS R-8 (GROUTED)	108	CY	
44		0855-0003	PUMPED WATER FILTER BAG	1	EA	
45		0855-0004	REPLACEMENT PUMPED WATER FILTER BAG	1	EA	
46		0867-0012	COMPOST FILTER SOCK 12" DIAMETER	474	LF	
47		0901-0001	MAINTENANCE AND PROTECTION OF TRAFFIC DURING CONSTRUCTION	1	LS	
48		0901-0240	ADDITIONAL TRAFFIC CONTROL SIGNS	200	SF	
49		0901-0320	4" STANDARD PAVEMENT MARKINGS PAINT & BEADS YELLOW	764	LF	
50		0901-0330	4" STANDARD PAVEMENT MARKINGS PAINT & BEADS WHITE	764	LF	
51		0931-0001	POST MOUNTED SIGNS TYPE B	3	SF	
52		0937-0114	GUIDE RAIL MOUNTED DELINEATOR TYPE D (W/W)	12	EA	

**BID DATE: 02/11/2021  
KINSLEY NO. 213010**

Line No.	Alt Code	Item No.	Short Description	QTY	Unit	Unit Price
53		0937-0339	FLEXIBLE DELINEATOR POST GROUND-MOUNT TYPE GM-2 RED POST WITH WHITE/BLANK SHEETING	3	EA	
54		0962-1000	4" WHITE WATERBORNE PAVEMENT MARKINGS	764	LF	
55		0962-1005	4" YELLOW WATERBORNE PAVEMENT MARKINGS	764	LF	
56		1018-0001	REMOVAL OF EXISTING BRIDGE	1	LS	
57		1091-0335	EPOXY INJECTION CRACK SEAL	1500	DOL	1
58	10	8020-0001	BRIDGE STRUCTURE AS DESIGNED S-38938	1	LS	
			PRECAST REINFORCED CONCRETE U-CHANNEL ABUTMENT	83	LF	
			PRECAST REINFORCED CONCRETE BOX END SECTIONS	2	EA	
			PRECAST REINFORCED CONCRETE SLABS	7	EA	
		1080-0473	PRESTRESSED CONCRETE PLANK BEAMS, 48" X 12"	304	LF	
		0204-0100	CLASS 3 EXCAVATION	525	CY	
		0620-0594	STRUCTURE MOUNTED GUIDE RAIL	70	LF	
		0680-0121	MEMBRANE WATERPROOFING SYSTEM INSTALLED ON OTHER SURFACES	76	SY	
		0703-0024	NO. 2A COARSE AGGREGATE	282	CY	
		0703-0025	NO. 57 COARSE AGGREGATE	26	CY	
		1001-1000	CLASS AAAP CEMENT CONCRETE	39	CY	
		1001-1060	CLASS AAA CEMENT CONCRETE	29	CY	
		1001-1080	CLASS AA CEMENT CONCRETE	3	CY	
		1001-1120	CLASS A CEMENT CONCRETE	7	CY	
		1001-0611	6" STRUCTURE FOUNDATION DRAIN	132	LF	
		0205-0297	STRUCTURE BACKFILL, COARSE AGGREGATE NO. 57	64	CY	
		1001-0980	MECHANICAL TEXTURING WITH LONGITUDINAL SAWED GROOVES	118	SY	
59	10	1002-0053	REINFORCEMENT BARS EPOXY COATED	3869	LB	
60	10	1002-0220	STAINLESS STEEL REINFORCEMENT BARS	213	LB	
61	10	1019-0050	PROTECTIVE COATING FOR REINFORCED CONCRETE SURFACES (PENETRATING SEALERS BRIDGE SUPERSTRUCTURE)	147	SY	
62	10	9000-0004	OVEREXCAVATION AND BACKFILL WITH NO. 2A COARSE AGGREGATE	36	CY	
63	11	8510-0001	PRECAST REINFORCED CONCRETE BOX CULVERT	1	LS	
64	12	8520-0001	CAST-IN-PLACE REINFORCED CONCRETE BOX CULVERT	1	LS	
65		9000-0001	TEMPORARY PUMP BYPASS	1	EA	
66		9000-0002	TEMPORARY COFFERDAM	113	LF	
67		9000-0003	STOCKPILING AND PLACEMENT OF NATURAL STREAMBED MATERIAL	71	CY	
68		9000-0005	MAILBOX RELOCATION	4	EA	
69		9000-0100	COVID-19 SAFETY PLAN SIGN	2	EA	