

ITEMS PennDOT ECMS 78906

<u>ALT</u>	<u>Item</u>	<u>Unit of Measure</u>	<u>Quantity</u>	<u>Unit Price</u>	<u>Item Total</u>	<u>FC</u>	<u>PDP</u>	<u>Mod Desc</u>	<u>CIS</u>	<u>WCC</u>	<u>Spec Prov</u>	<u>Action</u>
	4201-0001	Lump Sum	1.000			01	N	Yes		A	Proj	
		CLEARING AND GRUBBING MODIFIED										
	0203-0001	Cubic Yard	388.000			01	N			C		
		CLASS 1 EXCAVATION										
	0203-0006	Linear Foot	51.000			01	N			G4		
		SAW CUTTING										
	0212-0001	Linear Foot	64.000			01	N			C3, H, M2		
		GEOTEXTILE, CLASS 1										
	0212-0014	Square Yard	1,110.000			01	N			C3, H, M2		
		GEOTEXTILE, CLASS 4, TYPE A										
	0313-0320	Square Yard	575.000			01	N			E		
		SUPERPAVE ASPHALT MIXTURE DESIGN, BASE COURSE, PG 64S-22, < 0.3 MILLION ESALS, 25.0 MM MIX, 3" DEPTH										
	0350-0106	Square Yard	675.000			01	N			C, E		
		SUBBASE 6" DEPTH (NO. 2A)										
	0413-0191	Square Yard	950.000			01	N			F		
		SUPERPAVE ASPHALT MIXTURE DESIGN, WEARING COURSE, PG 64S-22, < 0.3 MILLION ESALS, 9.5 MM MIX, 1 1/2" DEPTH, SRL-E										

0413-6035	Square Yard	575.000	01 N	F	
	SUPERPAVE ASPHALT MIXTURE DESIGN, BINDER COURSE, PG 64S-22, < 0.3 MILLION ESALS, 19.0 MM MIX, 2 1/2" DEPTH				
0460-0001	Square Yard	1,525.000	01 N	F4	
	ASPHALT TACK COAT				
0491-0012	Square Yard	375.000	01 N	F3	
	MILLING OF ASPHALT PAVEMENT SURFACE, 1 1/2" DEPTH, MILLED MATERIAL RETAINED BY CONTRACTOR				
0608-0001	Lump Sum	1.000	06 N	X	
	MOBILIZATION				
0609-0007	Lump Sum	1.000	08 N	X	
	INSPECTOR'S FIELD OFFICE AND INSPECTION FACILITIES, TYPE B				
0609-0009	Lump Sum	1.000	08 N	X	Std
	EQUIPMENT PACKAGE				
0610-7002	Linear Foot	64.000	01 N	H2	
	6" PAVEMENT BASE DRAIN				
0615-0022	Linear Foot	40.000	01 N	H2	
	6" SUBSURFACE DRAIN OUTLETS				
0615-0050	Each	4.000	01 N	H2	
	SUBSURFACE DRAIN OUTLET ENDWALL (SLOPED)				

0615-0066	Each	4.000	01 N	C1, H2, R
66" RED SUBSURFACE DRAIN OUTLET MARKER				
0619-0459	Each	3.000	01 N	J1, J3
PERMANENT IMPACT ATTENUATING DEVICE, TYPE II, TEST LEVEL 3, TANGENT (MASH)				
0620-0010	Each	4.000	01 N	J
TYPICAL AND ALTERNATE CONCRETE BRIDGE BARRIER TRANSITION WITHOUT INLET PLACEMENT				
0620-0400	Each	1.000	01 N	J
TERMINAL SECTION, SINGLE				
0620-0503	Linear Foot	1,590.000	01 N	C1, J
REMOVE EXISTING GUIDE RAIL (CONTRACTOR'S PROPERTY)				
0620-0900	Each	3.000	01 N	C1, J
REMOVE CONCRETE ANCHORAGE				
0620-1600	Linear Foot	375.000	01 N	J
TYPE 31-S GUIDE RAIL				
0620-1602	Linear Foot	775.000	01 N	J
TYPE 31-S GUIDE RAIL WITH 8' EXTRA LENGTH POSTS				
0620-1625	Linear Foot	50.000	01 N	J
TYPE 31-SC GUIDE RAIL				
0686-0050	Lump Sum	1.000	01 N	X

CONSTRUCTION SURVEYING, TYPE D

[0689-0003](#) Lump Sum 1.000 01 N X

CPM SCHEDULE

[0690-0002](#) Dollar 6,000.000 \$1.00 \$6,000.00 08 Y X

SEMI-FORMAL FACILITATION

[0802-0001](#) Cubic Yard 39.000 01 N C1, M

TOPSOIL FURNISHED AND PLACED

[0804-0001](#) Pound 2.000 01 N M3

SEEDING AND SOIL SUPPLEMENTS - FORMULA B, INCLUDING MULCH

[0804-0003](#) Pound 15.000 01 N M3

SEEDING AND SOIL SUPPLEMENTS - FORMULA D, INCLUDING MULCH

[0804-0014](#) Pound 10.000 01 N M3

SEEDING - FORMULA E

[0810-0050](#) Lump Sum 1.000 01 N A, M1 [Proj](#)

SELECTIVE TREE REMOVAL

[0811-0003](#) Linear Foot 252.000 01 N J2, M

TEMPORARY PROTECTIVE FENCE

[0845-0001](#) Dollar 1,000.000 \$1.00 \$1,000.00 01 Y M2

UNFORESEEN WATER POLLUTION CONTROL

0849-0010	Each	2.000	01 N	C1	
	ROCK CONSTRUCTION ENTRANCE				
0850-0032	Cubic Yard	249.000	01 N	C1	
	ROCK, CLASS R-4				
0867-0018	Linear Foot	619.000	01 N	M2	
	COMPOST FILTER SOCK, 18" DIAMETER				
0901-0001	Lump Sum	1.000	07 N	Q	Proj
	MAINTENANCE AND PROTECTION OF TRAFFIC DURING CONSTRUCTION				
0901-0240	Square Foot	200.000	07 N	Q, R	
	ADDITIONAL TRAFFIC CONTROL SIGNS				
0901-0320	Linear Foot	730.000	07 N	O	
	4" STANDARD PAVEMENT MARKINGS, PAINT & BEADS, YELLOW				
0901-0330	Linear Foot	745.000	07 N	O	
	4" STANDARD PAVEMENT MARKINGS, PAINT & BEADS, WHITE				
0931-0001	Square Foot	13.000	01 N	R	
	POST MOUNTED SIGNS, TYPE B				
0935-0001	Square Foot	12.000	01 N	R	
	POST MOUNTED SIGNS, TYPE F				
0937-0339	Each	3.000	01 N	R	

FLEXIBLE DELINEATOR POST, GROUND-MOUNT TYPE GM-2, RED POST WITH WHITE/BLANK SHEETING

[0962-1000](#) Linear Foot 745.000 01 N O

4" WHITE WATERBORNE PAVEMENT MARKINGS

[0962-1005](#) Linear Foot 730.000 01 N O

4" YELLOW WATERBORNE PAVEMENT MARKINGS

[0971-0001](#) Each 5.000 01 N R

REMOVE POST MOUNTED SIGNS, TYPE B

[1018-0050](#) Lump Sum 1.000 20 N T1 [Proj](#)

REMOVAL OF PORTION OF EXISTING BRIDGE

[E](#) [8010-0001](#) Lump Sum 1.000 20 N S1 [Std](#)

BRIDGE STRUCTURE, AS DESIGNED, S-39536

[A](#) [1002-0052](#) Pound 19,690.000 20 N S7

REINFORCEMENT BARS, EPOXY COATED

[O](#) [8100-0001](#) Lump Sum 1.000 20 N S1 [Std](#)

STEEL BRIDGE STRUCTURE

[9000-0001](#) Linear Foot 240.000 01 N J2 [Proj](#)

REMOVE AND RESET FENCE

[9000-0002](#) Each 1.000 01 N J [Proj](#)

REMOVE AND RESET MAILBOX

[9000-0003](#) Dollar 5,000.000 \$1.00 \$5,000.00 01 Y X [Proj](#)

DETOUR ROUTE PAVEMENT REPAIR