

**BID DATE: 12/09/2021**  
**KINSLEY NO. 213140**

Line No.	Alt Code	Item No.	Short Description	QTY	Unit	Unit Price
1		0201-0001	CLEARING AND GRUBBING SR 441-031	1	LS	
2		0201-0002	CLEARING AND GRUBBING SR 441-033	1	LS	
3		0203-0001	CLASS 1 EXCAVATION	3042	CY	
4		0203-0006	SAW CUTTING	144	LF	
5		0205-0100	FOREIGN BORROW EXCAVATION	360	CY	
6		0212-0014	GEOTEXTILE CLASS 4 TYPE A	92	SY	
7		0313-0426	SP BASE PG64S-22 0.3TO<3 MILLION ESALs 25.0 MM 6" DEPTH	800	SY	
8		0350-0106	SUBBASE 6" DEPTH (NO. 2A)	800	SY	
9		0350-0121	SUBBASE (NO. 2A)	36	TON	
10		0413-0231	SP WEARING PG64S-22 0.3TO<3 MILLION ESALs 12.5 MM 2" DEPTH SRL-G	800	SY	
11		0413-6046	SP BINDER PG64S-22 0.3TO<3 MILLION ESALs 19.0 MIX 3" DEPTH	800	SY	
12		0460-0001	ASPHALT TACK COAT	1600	SY	
13		0608-0001	MOBILIZATION	1	LS	
14		0609-0003	INSPECTOR'S FIELD OFFICE AND INSPECTION FACILITIES TYPE B	1	LS	
15		0609-0009	EQUIPMENT PACKAGE	1	LS	
16		0619-0459	PERMANENT IMPACT ATTENUATING DEVICE TYPE II TEST LEVEL 3 TANGENT (MASH)	5	EA	
17		0620-0503	REMOVE EXISTING GUIDE RAIL (CONTRACTOR'S PROPERTY)	1549	LF	
18		0620-1600	TYPE 31-S GUIDE RAIL	1969	LF	
19		0620-1660	TYPE 31-STRONG POST ANCHOR TERMINAL	3	EA	
20		0686-0060	CONSTRUCTION SURVEYING TYPE D MODIFIED SR 441-031	1	LS	
21		0686-0061	CONSTRUCTION SURVEYING TYPE D MODIFIED SR 441-033	1	LS	
22		0689-0003	CPM SCHEDULE	1	LS	
23		0703-0025	NO. 57 COARSE AGGREGATE	35	CY	
24		0802-0001	TOPSOIL FURNISHED AND PLACED	77	CY	
25		0804-0004	SEEDING - FORMULA E INCLUDING MULCH	9	LB	
26		0804-0005	SEEDING AND SOIL SUPPLEMENTS - FORMULA N INCLUDING MULCH	23	LB	
27		0806-0112	TEMPORARY SHORT-TERM ROLLED EROSION CONTROL PRODUCT TYPE 2C	599	SY	
28		0845-0001	UNFORESEEN WATER POLLUTION CONTROL	2000	DOL	1
29		0850-0032	ROCK CLASS R-4	8	CY	
30		0850-0035	ROCK CLASS R-7	72	CY	
31		0855-0003	PUMPED WATER FILTER BAG	4	EA	
32		0855-0004	REPLACEMENT PUMPED WATER FILTER BAG	4	EA	
33		0867-0018	COMPOST FILTER SOCK 18" DIAMETER	465	LF	
34		0901-0001	MAINTENANCE AND PROTECTION OF TRAFFIC DURING CONSTRUCTION SR 441-031	1	LS	
35		0901-0002	MAINTENANCE AND PROTECTION OF TRAFFIC DURING CONSTRUCTION SR 441-033	1	LS	
36		0901-0240	ADDITIONAL TRAFFIC CONTROL SIGNS	200	SF	
37		0901-0460	FULL-MATRIX CHANGEABLE MESSAGE SIGN WITH TELECOMMUNICATIONS	5	EA	
38		0937-0339	FLEXIBLE DELINEATOR POST GROUND-MOUNT TYPE GM-2 RED POST WITH WHITE/BLANK SHEETING	8	EA	
39		0962-1000	4" WHITE WATERBORNE PAVEMENT MARKINGS	4600	LF	
40		0962-1005	4" YELLOW WATERBORNE PAVEMENT MARKINGS	4600	LF	
41		1018-0001	REMOVAL OF EXISTING BRIDGE SR 441-031	1	LS	
42		1018-0002	REMOVAL OF EXISTING BRIDGE SR 441-033	1	LS	
43	10	8510-0001	<b>PRECAST CONCRETE BOX CULVERT AS DESIGNED S-40077 SR 441-031</b>	1	LS	
		0204-0100	CLASS 3 EXCAVATION	165	CY	
		0680-0121	MEMBRANE WATERPROOFING SYSTEM INSTALLED ON OTHER SURFACES	112	SY	
		0703-0025	NO. 57 COARSE AGGREGATE	4	CY	
		1001-1120	CLASS A CEMENT CONCRETE	7	CY	
		0205-0292	STRUCTURE BACKFILL	75	CY	
			10'-0" X 8'-0" PRECAST REINFORCED CONCRETE BOX CULVERT SEGMENTS	55	LF	
			PRECAST REINFORCED CONCRETE END SECTIONS	2	EA	
			NO. 8 COARSE AGGREGATE	44	CY	
			NO. 2A COARSE AGGREGATE	80	CY	
			R-6 ROCK SELECT BORROW EXCAVATION	41	CY	
44	11	8510-0010	ALT. PRECAST CONCRETE BOX CULVERT	1	LS	

**BID DATE: 12/09/2021  
KINSLEY NO. 213140**

Line No.	Alt Code	Item No.	Short Description	QTY	Unit	Unit Price
45	20	8510-0002	PRECAST CONCRETE BOX CULVERT AS DESIGNED S-40078 SR 441-033	1	LS	
		0204-0100	CLASS 3 EXCAVATION	398	CY	
		0680-0121	MEMBRANE WATERPROOFING SYSTEM INSTALLED ON OTHER SURFACES	252	SY	
		0703-0025	NO. 57 COARSE AGGREGATE	7	CY	
		1001-1120	CLASS A CEMENT CONCRETE	10	CY	
		0205-0292	STRUCTURE BACKFILL	149	CY	
			13'-0" X 8'-6" PRECAST REINFORCED CONCRETE BOX CULVERT SEGMENTS	95	LF	
			PRECAST REINFORCED CONCRETE END SECTIONS	2	EA	
			NO. 8 COARSE AGGREGATE	83	CY	
			NO. 2A COARSE AGGREGATE	68	CY	
			R-6 ROCK SELECT BORROW EXCAVATION	46	CY	
46	21	8510-0020	ALT. PRECAST CONCRETE BOX CULVERT	1	LS	
47		9000-0001	TEMPORARY COFFERDAM SR 441-031	28	LF	
48		9000-0002	OVEREXCAVATION AND BACKFILLING UNDER FOUNDATIONS	102	CY	
49		9000-0003	TEMPORARY PUMP AND BYPASS SYSTEM SR 441-031	1	LS	
50		9000-0004	TEMPORARY PUMP AND BYPASS SYSTEM SR 441-033	1	LS	
51		9000-0005	TEMPORARY COFFERDAM SR 441-033	44	LF	
52		9000-0010	REMOVE RELOCATE AND REINSTALL FENCE SR 441-033	1	LS	
53		9000-0012	TEMPORARY PROTECTIVE FENCE SR 441-033	91	LF	