

BID DATE: 12/16/2021
KINSLEY NO. 213142

Line No.	Alt Code	Item No.	Short Description	QTY	Unit	Unit Price
1		0201-0001	CLEARING AND GRUBBING	1	LS	
2		0203-0001	CLASS 1 EXCAVATION	472	CY	
3		0203-0006	SAW CUTTING	451	LF	
4		0205-0100	FOREIGN BORROW EXCAVATION	180	CY	
5		0205-0264	SELECTED BORROW EXCAVATION ROCK CLASS R-4	129	CY	
6		0212-0014	GEOTEXTILE CLASS 4 TYPE A	213	SY	
7		0313-0426	SP BASE PG64S-22 0.3TO<3 MILLION ESALs 25.0 MM 6" DEPTH	171	SY	
8		0313-0436	SP BASE PG64S-22 0.3TO<3 MILLION ESALs 25.0 MM 12 " DEPTH	26	SY	
9		0350-0108	SUBBASE 8" DEPTH (NO. 2A)	411	SY	
10		0350-0120	SUBBASE (NO. 2A)	165	CY	
11		0413-0384	SP WEARING PG64E-22 0.3 TO < 3 MILLION ESALS 9.5 MM 1 1/2" DEPTH SRL-G	1017	SY	
12		0413-2072	SP WEARING (LEVELING) PG64S-22 0.3TO<3 MILLION ESALs 9.5 MM SRL-G	62	TON	
13		0413-6045	SP BINDER PG64S-22 0.3TO<3 MILLION ESALs 19.0 MM 2 1/2" DEPTH	196	SY	
14		0413-7008	SP BINDER (LEVELING) PG64S-22 0.3TO<3 MILLION ESALs 25.0 MM MIX	56	TON	
15		0460-0001	ASPHALT TACK COAT	1214	SY	
16		0491-0019	MILLING OF ASPHALT PAVEMENT SURFACE VARIABLE DEPTH MILLED MATERIAL RETAINED BY CONTRACTOR	821	SY	
17		0608-0001	MOBILIZATION	1	LS	
18		0609-0007	INSPECTOR'S FIELD OFFICE AND INSPECTION FACILITIES TYPE B	1	LS	
19		0609-0009	EQUIPMENT PACKAGE	1	LS	
20		0619-0459	PERMANENT IMPACT ATTENUATING DEVICE TYPE II TEST LEVEL 3 TANGENT (MASH)	3	EA	
21		0620-0400	TERMINAL SECTION SINGLE	1	EA	
22		0620-0503	REMOVE EXISTING GUIDE RAIL (CONTRACTOR'S PROPERTY)	275	LF	
23		0620-1600	TYPE 31-S GUIDE RAIL	263	LF	
24		0620-1645	CURVED W-BEAM GUIDE RAIL AT INTERSECTIONS	13	LF	
25		0620-1670	TYPE 31-STRONG POST IN-LINE ANCHOR	1	EA	
26		0620-2020	THRIE-BEAM GUIDE RAIL TO PA BRIDGE BARRIER TRANSITION WITHOUT CURB	4	EA	
27		0686-0020	CONSTRUCTION SURVEYING TYPE B	1	LS	
28		0686-0050	CONSTRUCTION SURVEYING TYPE D	1	LS	
29		0689-0003	CPM SCHEDULE	1	LS	
30		0690-0001	INTERNAL FACILITATION	1000	DOL	1
31		0802-0001	TOPSOIL FURNISHED AND PLACED	163	CY	
32		0804-0001	SEEDING AND SOIL SUPPLEMENTS - FORMULA B INCLUDING MULCH	62	LB	
33		0804-0003	SEEDING AND SOIL SUPPLEMENTS - FORMULA D INCLUDING MULCH	10	LB	
34		0804-0004	SEEDING - FORMULA E INCLUDING MULCH	18	LB	
35		0804-0006	SEEDING AND SOIL SUPPLEMENTS - FORMULA L INCLUDING MULCH	14	LB	
36		0804-0007	SEEDING AND SOIL SUPPLEMENTS - FORMULA W INCLUDING MULCH	8	LB	
37		0806-0113	TEMPORARY SHORT-TERM ROLLED EROSION CONTROL PRODUCT TYPE 2D	1084	SY	
38		0810-0052	SELECTIVE TREE REMOVAL	4	EA	
39		0811-0003	TEMPORARY PROTECTIVE FENCE	365	LF	
40		0845-0001	UNFORESEEN WATER POLLUTION CONTROL	5000	DOL	1
41		0849-0010	ROCK CONSTRUCTION ENTRANCE	1	EA	
42		0855-0003	PUMPED WATER FILTER BAG	3	EA	
43		0855-0004	REPLACEMENT PUMPED WATER FILTER BAG	3	EA	
44		0867-0012	COMPOST FILTER SOCK 12" DIAMETER	255	LF	
45		0901-0001	MAINTENANCE AND PROTECTION OF TRAFFIC DURING CONSTRUCTION	1	LS	
46		0901-0240	ADDITIONAL TRAFFIC CONTROL SIGNS	58	SF	
47		0901-0320	4" STANDARD PAVEMENT MARKINGS PAINT & BEADS YELLOW	1604	LF	
48		0901-0330	4" STANDARD PAVEMENT MARKINGS PAINT & BEADS WHITE	1623	LF	
49		0901-0451	3-LINE CHANGEABLE MESSAGE SIGN WITHOUT TELECOMMUNICATIONS	2	EA	
50		0931-0001	POST MOUNTED SIGNS TYPE B	37	SF	
51		0935-0001	POST MOUNTED SIGNS TYPE F	23	SF	
52		0962-1000	4" WHITE WATERBORNE PAVEMENT MARKINGS	1623	LF	
53		0962-1005	4" YELLOW WATERBORNE PAVEMENT MARKINGS	1604	LF	
54		1002-0053	REINFORCEMENT BARS EPOXY COATED	42953	LB	
55		1002-0220	STAINLESS STEEL REINFORCEMENT BARS	200	LB	
56		1018-0001	REMOVAL OF EXISTING BRIDGE	1	LS	

**BID DATE: 12/16/2021
KINSLEY NO. 213142**

Line No.	Alt Code	Item No.	Short Description	QTY	Unit	Unit Price
57		1019-0050	PROTECTIVE COATING FOR REINFORCED CONCRETE SURFACES (PENETRATING SEALERS BRIDGE SUPERSTRUCTURE)	320	SY	
58		8010-0001	BRIDGE STRUCTURE AS DESIGNED S-40376	1	LS	
			PRECAST CONCRETE FOOTING PANELS	68	CY	
			PRECAST CONCRETE STEM PANELS	74	CY	
		0204-0100	CLASS 3 EXCAVATION	686	CY	
		0680-0121	MEMBRANE WATERPROOFING SYSTEM INSTALLED ON OTHER SURFACES	87	SY	
		0703-0025	NO. 57 COARSE AGGREGATE	20	CY	
		1001-1000	CLASS AAAP CEMENT CONCRETE	30	CY	
		1001-1080	CLASS AA CEMENT CONCRETE	109	CY	
		1089-0001	PA BRIDGE BARRIER	101	LF	
		0205-0292	STRUCTURE BACKFILL	686	CY	
		1080-0403	PRESTRESSED CONCRETE SPREAD BOX BEAMS 36" X 21"	124	LF	
		1001-0611	6" STRUCTURE FOUNDATION DRAIN	70	LF	
			6" PVC PIPE (SCHEDULE 40)	25	LF	
		1001-0980	MECHANICAL TEXTURING WITH LONGITUDINAL SAWED GROOVES	265	SY	
59		9000-0001	HEALTH AND SAFETY PLAN	1	LS	
60		9000-0002	SITE WORK PLAN	1	LS	
61		9000-0003	MANAGEMENT OF CONTAMINATED GROUND WATER	90000	DOL	1
62		9000-0004	HANDLING AND DISPOSAL OF CONTAMINATED SOIL/SEDIMENT	743	TON	
63		9000-0005	SELECTED BORROW EXC. ROCK CLASS R-7 CHOKED WITH ROCK CLASS R-4	124	CY	
64		9000-0006	NO. 2A COARSE AGGREGATE WITH EXCAVATION	22	CY	
65		9000-0007	CLASS C CEMENT CONCRETE HES WITH EXCAVATION	22	CY	
66		9203-0101	TEMPORARY EXCAVATION SUPPORT AND PROTECTION SYSTEM	1	LS	