

**BID DATE: 01/13/2022  
KINSLEY NO. 223004**

Line No.	Alt Code	Item No.	Short Description	QTY	Unit	Unit Price
1		0201-0001	CLEARING AND GRUBBING	1	LS	
2		0203-0001	CLASS 1 EXCAVATION	140	CY	
3		0203-0004	CLASS 1B EXCAVATION	70	CY	
4		0203-0006	SAW CUTTING	75	LF	
5		0204-0100	CLASS 3 EXCAVATION	166	CY	
6		0205-0292	STRUCTURE BACKFILL	76	CY	
7		0212-0001	GEOTEXTILE CLASS 1	103	LF	
8		0212-0014	GEOTEXTILE CLASS 4 TYPE A	313	SY	
9		0213-0002	TEMPORARY PROJECT AIR POLLUTION CONTROL	1000	DOL	1
10		0313-0426	SP BASE PG64S-22 0.3TO<3 MILLION ESALs 25.0 MM MIX 6" DEPTH	471	SY	
11		0316-0437	SP FLEXIBLE BASE REPLACEMENT PG64S-22 0.3TO<3 MILLION ESALs 25.0 MM MIX	4	TON	
12		0350-0106	SUBBASE 6" DEPTH (NO. 2A)	471	SY	
13		0413-0246	SP WEARING PG64S-22 0.3TO<3 MILLION ESALs 9.5 MM MIX 1 1/2" DEPTH SRL-G	1718	SY	
14		0413-1024	SP WEARING (SCRATCH) PG64S-22 0.3TO<3 MILLION ESALs 9.5 MM MIX SRL-L	36	TON	
15		0413-6045	SP BINDER PG64S-22 0.3TO<3 MILLION ESALs 19.0 MM MIX 2 1/2" DEPTH	313	SY	
16		0460-0003	ASPHALT TACK COAT (NTT/CNTT)	3120	SY	
17		0491-0013	MILLING OF ASPHALT PAVEMENT 2" DEPTH MILLED MATERIAL RETAINED BY CONTRACTOR	1247	SY	
18	10	0601-0333	18" THERMOPLASTIC PIPE GROUP II 12'-1.5' FILL	12	LF	
19	11	0601-9653	18" CORRUGATED GALV. STEEL PIPE TYPE I POLYMER COATED (2 2/3" X 1/2" CORR.) 16 GAGE	12	LF	
20		0601-5431	CLASS C CEMENT CONCRETE FOR MISCELLANEOUS DRAINAGE	1	CY	
21		0605-2700	INLET GRATE	1	EA	
22		0605-2711	TYPE C CONCRETE TOP UNIT AND BICYCLE SAFE GRATE	1	SET	
23		0605-2850	STANDARD INLET BOX HEIGHT < />= 10'	1	EA	
24		0605-5701	TYPE C CONCRETE TOP UNIT 4" CURB HEIGHT AND BICYCLE SAFE GRATE	1	SET	
25		0608-0001	MOBILIZATION	1	LS	
26		0609-0007	INSPECTOR'S FIELD OFFICE AND INSPECTION FACILITIES TYPE B	1	LS	
27		0609-0009	EQUIPMENT PACKAGE	1	LS	
28		0610-7002	6" PAVEMENT BASE DRAIN	103	LF	
29		0615-0022	6" SUBSURFACE DRAIN OUTLETS	20	LF	
30		0615-0040	SUBSURFACE DRAIN OUTLET ENDWALL	1	EA	
31		0615-0066	66" RED SUBSURFACE DRAIN OUTLET MARKER	1	EA	
32		0618-0022	CONCRETE COLLAR FOR 18" PIPE EXTENSION	1	EA	
33		0619-0459	PERMANENT IMPACT ATTENUATING DEVICE TYPE II TEST LEVEL 3 TANGENT (MASH)	1	EA	
34		0620-0400	TERMINAL SECTION SINGLE	2	EA	
35		0620-0503	REMOVE EXISTING GUIDE RAIL (CONTRACTOR'S PROPERTY)	888	LF	
36		0620-0872	BURIED-IN-BACKSLOPE TERMINAL SINGLE PANEL	1	EA	
37		0620-1600	TYPE 31-S GUIDE RAIL	588	LF	
38		0620-1625	TYPE 31-SC GUIDE RAIL	25	LF	
39		0620-1670	TYPE 31-STRONG POST IN-LINE ANCHOR	2	EA	
40		0620-2010	THRIE-BEAM GUIDE RAIL TO CONCRETE BRIDGE BARRIER TRANSITION WITHOUT CURB	3	EA	
41		0620-2011	THRIE-BEAM GUIDE RAIL TO CONCRETE BRIDGE BARRIER TRANSITION WITH CURB AND INLET	1	EA	
42		0627-3019	TEMPORARY BARRIER TEST LEVEL 3 BARRIER DEFLECTION DISTANCE < />=1'	312	LF	
43		0628-3019	RESET TEMPORARY BARRIER TEST LEVEL 3 BARRIER DEFLECTION DISTANCE < />=1'	288	LF	
44		0630-0001	PLAIN CEMENT CONCRETE CURB	52	LF	
45		0676-0001	CEMENT CONCRETE SIDEWALK	25	SY	
46		0686-0050	CONSTRUCTION SURVEYING TYPE D	1	LS	
47		0689-0003	CPM SCHEDULE	1	LS	
48		0690-0001	INTERNAL FACILITATION	1000	DOL	1
49	20	0695-0002	DETECTABLE WARNING SURFACE CAST IRON	9	SF	
50	21	0695-0003	DETECTABLE WARNING SURFACE POLYMER CONCRETE	9	SF	
51	22	0695-0004	DETECTABLE WARNING SURFACE POLYMER COMPOSITE	9	SF	
52		0696-0610	TEMPORARY IMPACT ATTENUATING DEVICE TYPE V (STANDARD) TEST LEVEL 3	2	EA	
53		0697-0610	RESET TEMPORARY IMPACT ATTENUATING DEVICE TYPE V (STANDARD) TEST LEVEL 3	2	EA	
54		0804-0001	SEEDING AND SOIL SUPPLEMENTS - FORMULA B INCLUDING MULCH	8	LB	
55		0804-0006	SEEDING AND SOIL SUPPLEMENTS - FORMULA L INCLUDING MULCH	9	LB	
56		0806-0113	TEMPORARY SHORT-TERM ROLLED EROSION CONTROL PRODUCT TYPE 2D	182	SY	
57		0850-0031	ROCK CLASS R-3	2	CY	
58		0850-0032	ROCK CLASS R-4	4	CY	
59		0860-0002	INLET FILTER BAG FOR TYPE C INLET	2	EA	

**PENNDOT SR 1015-015 PERRY COUNTY**

**BID ITEMS**

**PENNDOT PROJECT NO. 100372**

PAGE 1 OF 2

**BID DATE: 01/13/2022  
KINSLEY NO. 223004**

Line No.	Alt Code	Item No.	Short Description	QTY	Unit	Unit Price
60		0867-0012	COMPOST FILTER SOCK 12" DIAMETER	546	LF	
61		0901-0001	MAINTENANCE AND PROTECTION OF TRAFFIC DURING CONSTRUCTION	1	LS	
62		0901-0203	ARROW PANEL	2	EA	
63		0901-0231	ADDITIONAL WARNING LIGHTS TYPE B	100	DAY	
64		0901-0232	ADDITIONAL WARNING LIGHTS TYPE C	100	DAY	
65		0901-0240	ADDITIONAL TRAFFIC CONTROL SIGNS	300	SF	
66		0901-0320	4" STANDARD PAVEMENT MARKINGS PAINT & BEADS YELLOW	4108	LF	
67		0901-0330	4" STANDARD PAVEMENT MARKINGS PAINT & BEADS WHITE	5037	LF	
68		0901-0334	24" STANDARD PAVEMENT MARKINGS PAINT & BEADS WHITE	108	LF	
69		0901-0461	FULL-MATRIX CHANGEABLE MESSAGE SIGN WITHOUT TELECOMMUNICATIONS	5	EA	
70		0931-0003	POST MOUNTED SIGNS TYPE B STEEL SQUARE POST	111	SF	
71		0935-0001	POST MOUNTED SIGNS TYPE F	102	SF	
72		0937-0107	GUIDE RAIL MOUNTED DELINEATOR TYPE B (W/W)	14	EA	
73		0937-0114	GUIDE RAIL MOUNTED DELINEATOR TYPE D (W/W)	14	EA	
74		0937-0334	FLEXIBLE DEL. POST GROUND-MOUNT TYPE GM-2 YELLOW POST WITH YEL/YEL SHEETING	2	EA	
75		0945-0001	RESET POST MOUNTED SIGNS TYPE F	2	EA	
76	30	0958-0121	TEMP. TRAFFIC CONTROL SIGNALS TRAILER-MNTD PORTABLE DEVICE (2-OVERHEAD SIGNALS)	4	EA	
77	30	0958-0261	TEMPORARY TRAFFIC CONTROL SIGNAL TRAILER-MOUNTED PORTABLE DEVICE RESET	4	EA	
78	31	0958-0041	TEMPORARY TRAFFIC CONTROL SIGNALS ON FIXED SUPPORTS (4 OR MORE APPROACHES)	1	EA	
79		0960-0230	WHITE HOT THERMOPLASTIC LEGEND "WRONG WAY ARROW" 23' - 0"	2	EA	
80		0962-1000	4" WHITE WATERBORNE PAVEMENT MARKINGS	2390	LF	
81		0962-1005	4" YELLOW WATERBORNE PAVEMENT MARKINGS	2040	LF	
82		0963-0001	PAVEMENT MARKING REMOVAL	1926	SF	
83		1001-0980	MECHANICAL TEXTURING WITH LONGITUDINAL SAWED GROOVES	770	SY	
84		1001-1000	CLASS AAAP CEMENT CONCRETE	16	CY	
85		1001-1080	CLASS AA CEMENT CONCRETE	70	CY	
86		1002-0052	REINFORCEMENT BARS EPOXY COATED	10900	LB	
87		1002-0142	MECHANICAL SPLICE SYSTEM FOR NO. 6 REINFORCEMENT BARS EPOXY COATED	28	EA	
88		1003-0007	DOWEL HOLES 16" DEPTH	90	EA	
89		5018-0050	REMOVAL OF PORTION OF EXISTING BRIDGE	1	LS	
90		1019-0040	PROTECTIVE COATING FOR REINFORCED CONCRETE SURFACES (PENETRATING SEALERS REINFORCED CONCRETE SUBSTRUCTURE SURFACES)	642	SY	
91		1019-0050	PROTECTIVE COATING FOR REINFORCED CONCRETE SURFACES (PENETRATING SEALERS BRIDGE SUPERSTRUCTURE)	78	SY	
92		1026-0016	NEOPRENE STRIP SEAL DAM (3 1/2" MOVEMENT)	77	LF	
93		1039-0010	CONCRETE BRIDGE DECK SURFACE PREPARATION HYDRODEMOLITION	831	SY	
94		1040-0003	CONCRETE BRIDGE DECK REPAIR TYPE 3	374	SF	
95		1041-0010	SCARIFICATION 1/4" DEPTH	831	SY	
96		1042-0002	LATEX MODIFIED CONCRETE WEARING SURFACE 1 1/2" DEPTH	837	SY	
97		1042-0060	LATEX MODIFIED CONCRETE VARIABLE DEPTH	7	CY	
98		1050-0096	GRADE ADJUSTMENT OF EXISTING SCUPPER	2	EA	
99		1050-0100	UNFORSEEN FABRICATED STRUCTURAL STEEL REPAIRS	20000	DOL	1
100		1070-0200	PAINTING EXISTING STRUCTURAL STEEL	1	LS	
101		1070-0325	PRIMING TOP FLANGES	1	LS	
102		1072-0100	CONTAINMENT	1	LS	
103		1072-0200	WASTE MANAGEMENT	1	LS	
104		1072-0300	WORKER HEALTH AND SAFETY	1	LS	
105		1091-0335	EPOXY INJECTION CRACK SEAL	5000	DOL	1
106		9000-0001	NEOPRENE STRIP SEAL DAM (5" MOVEMENT)	77	LF	
107		9000-0002	MODIFY EXISTING BRIDGE BARRIER RAIL	1	LS	
108		9000-0003	CEMENT CONCRETE SPLASH BLOCKS	2	EA	
109		9000-0600	CLASS AA CEMENT CONCRETE REPAIRS	46	CF	
110		9000-0610	CLASS A CEMENT CONCRETE REPAIRS	664	CF	
111		9605-4001	CAP EXISTING INLET	1	EA	
112		9705-0103	TWO-PART RAPID CURE SILICONE JOINT SEALANT (BARRIER JOINTS)	199	LF	