

BID DATE: 01/13/2022

KINSLEY NO. 223002

Line No.	Alt Code	Item No.	Short Description	QTY	Unit	Unit Price
1		0201-0001	CLEARING AND GRUBBING	1	LS	
2		0203-0001	CLASS 1 EXCAVATION	3092	CY	
3		0204-0001	CLASS 2 EXCAVATION	28	CY	
4		0205-0264	SELECTED BORROW EXCAVATION ROCK CLASS R-4	101	CY	
5		0205-0266	SELECTED BORROW EXCAVATION ROCK CLASS R-6	1733	CY	
6		0212-0014	GEOTEXTILE CLASS 4 TYPE A	1675	SY	
7		0313-0425	SP BASE PG64S-22 0.3TO<3 MILLION ESALs 25.0 MM MIX 5 1/2" DEPTH	1083	SY	
8		0313-0437	SP BASE PG64S-22 0.3TO<3 MILLION ESALs 25.0 MM MIX	18	TON	
9		0350-0108	SUBBASE 8" DEPTH (NO. 2A)	1474	SY	
10		0350-0121	SUBBASE (NO. 2A)	13	TON	
11		0413-0247	SP WEARING PG64S-22 0.3TO<3 MILLION ESALs 9.5 MM MIX 1 1/2" DEPTH SRL-M	1083	SY	
12		0413-0257	SP WEARING PG64S-22 0.3TO<3 MILLION ESALs 9.5 MM MIX SRL-M	5	TON	
13		0460-0001	ASPHALT TACK COAT	1136	SY	
14		0491-0012	MILLING OF ASPHALT PAVEMENT SURFACE 1 1/2" DEPTH MILLED MATERIAL RETAINED BY CONTRACTOR	1136	SY	
15		0608-0001	MOBILIZATION	1	LS	
16		0609-0007	INSPECTOR'S FIELD OFFICE AND INSPECTION FACILITIES TYPE B	1	LS	
17		0609-0009	EQUIPMENT PACKAGE	1	LS	
18		0612-0001	SUBGRADE DRAINS	132	LF	
19		0619-0459	PERMANENT IMPACT ATTENUATING DEVICE TYPE II TEST LEVEL 3 TANGENT (MASH)	1	EA	
20		0620-0012	THRIE-BEAM TO PA TYPE 10M BRIDGE BARRIER TRANSITION WITHOUT INLET PLACEMENT	4	EA	
21		0620-0400	TERMINAL SECTION SINGLE	1	EA	
22		0620-0503	REMOVE EXISTING GUIDE RAIL (CONTRACTOR'S PROPERTY)	1086	LF	
23		0620-1600	TYPE 31-S GUIDE RAIL	363	LF	
24		0620-1601	TYPE 31-S GUIDE RAIL WITH 7' EXTRA LENGTH POSTS	150	LF	
25		0620-1626	TYPE 31-SC GUIDE RAIL WITH 7' EXTRA LENGTH POSTS	50	LF	
26		0620-1645	CURVED W-BEAM GUIDE RAIL AT INTERSECTIONS	25	LF	
27		0686-0050	CONSTRUCTION SURVEYING TYPE D	1	LS	
28		0689-0003	CPM SCHEDULE	1	LS	
29		0690-0001	INTERNAL FACILITATION	1000	DOL	1
30		0703-0020	NO. 1 COARSE AGGREGATE	189	CY	
31		0703-0024	NO. 2A COARSE AGGREGATE	217	CY	
32		0802-0001	TOPSOIL FURNISHED AND PLACED	172	CY	
33		0804-0013	SEEDING AND SOIL SUPPLEMENTS - FORMULA D	41	LB	
34		0804-0014	SEEDING - FORMULA E	32	LB	
35		0804-0020	SEEDING AND SOIL SUPPLEMENTS - FORMULA L	38	LB	
36		0804-0021	SEEDING AND SOIL SUPPLEMENTS - FORMULA W	4	LB	
37		0805-0022	MULCHING - STRAW	1	TON	
38		0806-0112	TEMPORARY SHORT-TERM ROLLED EROSION CONTROL PRODUCT TYPE 2C	1369	SY	
39		0811-0003	TEMPORARY PROTECTIVE FENCE	147	LF	
40		0845-0001	UNFORESEEN WATER POLLUTION CONTROL	1000	DOL	1
41		0850-0022	ROCK CLASS R-4	50	SY	
42		0855-0003	PUMPED WATER FILTER BAG	2	EA	
43		0855-0004	REPLACEMENT PUMPED WATER FILTER BAG	2	EA	
44		0867-0012	COMPOST FILTER SOCK 12" DIAMETER	878	LF	
45		0901-0001	MAINTENANCE AND PROTECTION OF TRAFFIC DURING CONSTRUCTION	1	LS	
46		0901-0240	ADDITIONAL TRAFFIC CONTROL SIGNS	100	SF	
47		0931-0003	POST MOUNTED SIGNS TYPE B STEEL SQUARE POST	21	SF	
48		0935-0001	POST MOUNTED SIGNS TYPE F	9	SF	
49		0962-1000	4" WHITE WATERBORNE PAVEMENT MARKINGS	3062	LF	
50		0962-1005	4" YELLOW WATERBORNE PAVEMENT MARKINGS	3200	LF	
51		0971-0001	REMOVE POST MOUNTED SIGNS TYPE B	2	EA	
52		5001-1140	CLASS C CEMENT CONCRETE (WITH OVEREXCAVATION)	36	CY	
53		5018-0001	REMOVAL OF EXISTING BRIDGE (S-2528)	1	LS	
54		1091-0331	EPOXY INJECTION CRACK SEAL	300	LF	
55		1999-0000	TRAINEES FOR PROJECTS 100% STATE FUNDED	1000	HR	
56	10	8010-0001	BRIDGE STRUCTURE AS DESIGNED S-38894	1	LS	
		0204-0100	CLASS 3 EXCAVATION	2232	CY	
		0212-0014	GEOTEXTILE, CLASS 4, TYPE A	404	SY	

PENNDOT SR 1901-001 LANCASTER COUNTY

BID ITEMS

PENNDOT PROJECT NO. 101036

PAGE 1 OF 2

BID DATE: 01/13/2022

KINSLEY NO. 223002

Line No.	Alt Code	Item No.	Short Description	QTY	Unit	Unit Price
		0680-0121	MEMBRANE WATERPROOFING SYSTEM INSTALLED ON OTHER SURFACES	158	SY	
		0703-0025	NO. 57 COARSE AGGREGATE	17	CY	
			SELECTED BORROW EXCAVATION ROCK, CLASS R-7 CHOKED WITH ROCK, CLASS R-4	1698	CY	
		1001-1000	CLASS AAAP CEMENT CONCRETE	290	CY	
		1001-1080	CLASS AA CEMENT CONCRETE	146	CY	
		1001-1120	CLASS A CEMENT CONCRETE	464	CY	
		1019-0050	PROTECTIVE COATING FOR REINFORCED CONCRETE SURFACES (PENETRATING SEALERS, BRIDGE SUPERSTRUCTURE)	1198	SY	
		1019-0040	PROTECTIVE COATING FOR REINFORCED CONCRETE SURFACES (PENETRATING SEALERS, REINFORCED CONCRETE SUBSTRUCTURE SURFACES)	574	SY	
		1001-0611	6" STRUCTURE FOUNDATION DRAIN	79	LF	
			6" PVC PIPE (SCHEDULE 40)	6	LF	
		0205-0292	STRUCTURE BACKFILL	1172	CY	
		1080-0435	PRESTRESSED CONCRETE SPREAD BOX BEAMS, 48" X 27"	1065	LF	
		1088-0001	PA TYPE 10M BRIDGE BARRIER	460	LF	
		1001-0980	MECHANICAL TEXTURING WITH LONGITUDINAL SAWED GROOVES	1008	SY	
			METAL CURB DRAIN	6	EA	
57	10	1002-0053	REINFORCEMENT BARS EPOXY COATED	142421	LB	
58	10	1002-0220	STAINLESS STEEL REINFORCEMENT BARS	506	LB	
59	11	8000-0001	PRESTRESSED CONCRETE BRIDGE STRUCTURE	1	LS	
60	12	8100-0001	STEEL BRIDGE STRUCTURE	1	LS	
61		9000-0001	COFFERDAM	154	LF	
62		9000-0002	RELOCATED FENCE	437	LF	
63		9000-0003	TEMPORARY MAILBOX RELOCATION	1	EA	
64		9000-0004	REMOVAL OF EXISTING METAL STEPS	1	EA	
65		9000-0006	AIDS TO NAVIGATION (ATON) PLAN	1	LS	
66		9000-0500	PERMANENT RIGHT-OF-WAY MONUMENTS	4	EA	
67		9203-0100	TEMPORARY EXCAVATION SUPPORT & PROTECTION SYSTEM S-38894	1	LS	